



SINGLE ZONE VERTICAL AIR HANDLING UNIT ENGINEERING MANUAL



LV181HV (18,000 Btu/h)
LV241HV (24,000 Btu/h)



LV300HV (30,000 Btu/h)
LV361HV (36,000 Btu/h)



LV420HV1 (42,000 Btu/h)
LV420HV2 (42,000 Btu/h)
LV480HV1 (48,000 Btu/h)
LV480HV2 (48,000 Btu/h)
LV600HV (60,000 Btu/h)

18,000 - 60,000 Btu/h

PROPRIETARY DATA NOTICE

This document, as well as all reports, illustrations, data, information, and other materials are the property of LG Electronics U.S.A., Inc., and are disclosed by LG Electronics U.S.A., Inc. only in confidence. This document is for design purposes only.

A summary list of safety precautions is on page 3.

Proper sizing and installation of equipment is critical to achieve optimal performance. Split system air conditioners and heat pumps (excluding ductless systems) must be matched with appropriate coil components to meet ENERGY STAR® criteria. Ask your contractor for details or visit www.energystar.gov.

(ENERGY STAR and the ENERGY STAR mark are registered trademarks owned by the U.S. Environmental Protection Agency.)

For more technical materials such as submittals, catalogs, installation, owner's, and service manuals, visit www.lghvac.com.

TABLE OF CONTENTS


Unit Nomenclature.....	4	Indoor Unit Wiring Diagram.....	37
LG Air Conditioner Technical Solution (LATS)	5	Outdoor Unit Wiring Diagram.....	40
Mechanical Specifications.....	8	Electrical Wiring	43
General Data	10	<i>NJ / NK Frame Wiring Diagram Legend</i>	43
<i>Pairing Table</i>	10	<i>DIP Switch Settings</i>	44
General Data / Specifications	12	Electrical Connections.....	45
Electrical Data.....	16	<i>Connections and Specifications</i>	48
Functions, Controls, and Options.....	17	External Static Pressure and AirFlow Ranges.....	52
<i>Indoor Unit</i>	17	Accessories	57
<i>Outdoor Unit</i>	18	Performance Data.....	62
Outdoor Unit Dimensions	19	<i>Cooling Capacity Tables</i>	62
<i>LUU180HV, LUU240HV</i>	19	<i>Heating Capacity Tables</i>	71
<i>LUU360HV, LUU420HV, LUU480HV, LUU601HV</i>	20	<i>Maximum Heating Capacity Tables</i>	80
Indoor Unit Dimensions	21	Equipment Selection Procedure	89
<i>LVN181HV4, LVN241HV4, LVN300HCV, LVN361HV4</i>	21	<i>Correction Factors</i>	89
<i>LVN420HV, LVN480HV, LVN600HV</i>	22	Placement Considerations	93
Acoustic Data.....	23	<i>Indoor Unit</i>	93
<i>Indoor Units Sound Pressure</i>	23	<i>Outdoor Unit</i>	94
<i>Indoor Units Sound Power</i>	26	Clearances	97
<i>Outdoor Units Sound Pressure</i>	29	<i>Outdoor Unit</i>	97
<i>Outdoor Units Sound Power</i>	31	Installing Outdoor Units Indoors	100
Refrigerant Flow Diagram.....	34	Refrigerant Piping Design	102
<i>Indoor Units</i>	34	<i>Design Guideline Summary</i>	102
<i>Outdoor Units</i>	35		

TABLE OF SYMBOLS

 DANGER	<i>This symbol indicates an imminently hazardous situation which, if not avoided, will result in death or serious injury.</i>
 WARNING	<i>This symbol indicates a potentially hazardous situation which, if not avoided, could result in death or serious injury.</i>
 CAUTION	<i>This symbol indicates a potentially hazardous situation which, if not avoided, may result in minor or moderate injury.</i>
Note:	<i>This symbol indicates situations that may result in equipment or property damage accidents only.</i>
	<i>This symbol indicates an action that must not be performed.</i>

UNIT NOMENCLATURE

Indoor Units and Outdoor Units



LG AIR CONDITIONER TECHNICAL SOLUTION (LATS)

LG Air Conditioner Technical Solution (LATS) Software

A properly designed and installed refrigerant piping system is critical to the optimal performance of LG air-conditioning systems. To assist engineers, LG offers, free of charge, LG Air Conditioner Technical Solution (LATS) software—a total design solution for LG air conditioning systems. Contact your LG Rep for the best software program for your application.

Note:

To reduce the risk of designing an improperly applied system or one that will not operate correctly, LG requires that LATS software be used on all projects.

Formats

LATS is available to LG customers in three user interfaces: LATS HVAC, LATS CAD2, and LATS Revit. All three LATS formats are available through www.myLGHVAC.com, or contact an LG Sales Representative.

LATS HVAC is a Windows®-based application that aids engineers in designing LG Variable Refrigerant Flow (VRF), Multi F / Multi F MAX, Single-Zone, and Energy Recovery Ventilator (ERV) systems.

*Windows® is a registered mark of Microsoft® Corporation.

LATS CAD2 combines the LG LATS program with AutoCAD® software**. It permits engineers to layout and validate LG Multi V Variable Refrigerant Flow (VRF), Multi F / Multi F MAX, Single-Zone, and Energy Recovery Ventilator (ERV) systems directly into CAD drawings.

LATS Revit integrates the LG LATS program with Revit® software**. It permits engineers to layout and validate Multi V VRF systems directly into Revit drawings.

**AutoCAD® and Revit® are both registered marks of Autodesk, Inc.

Features

All LG product design criteria have been loaded into the program, making LATS simple to use: double click or drag and drop the component choices. Build systems in Tree Mode where the refrigerant system can be viewed. Switch to a Schematic diagram to see the electrical and communications wiring.

LATS software permits the user to input region data, indoor and outdoor design temperatures, modify humidity default values, zoning, specify type and size of outdoor units and indoor units, and input air flow and external static pressure (ESP) for ducted indoor units.

The program can also:

- Import building loads from a separate Excel file.
- Present options for outdoor unit auto selection.
- Automatically calculate component capacity based on design conditions for the chosen region.
- Verify if the height differences between the various system components are within system limits.
- Provide the correct size of each refrigerant piping segment and LG Y-Branches and Headers.
- Adjust overall piping system length when elbows are added.
- Check for component piping limitations and flag if any parameters are broken.
- Factor operation and capacity for defrost operation.
- Calculate refrigerant charge, noting any additional trim charge.
- Suggest accessories for indoor units and outdoor units.
- Run system simulation.

Note:

Features depend on which LATS program is being used, and the type of system being designed.

Figure 1: Example of LATS CAD2.



LG AIR CONDITIONER TECHNICAL SOLUTION (LATS)

LATS Generates a Complete Project Report

LATS software also generates a report containing project design parameters, cooling and heating design data, system component performance, and capacity data. The report includes system combination ratio and refrigerant charge calculations; and provides detailed bill of material, including outdoor units, indoor units, control devices, accessories, refrigerant pipe sizes segregated by building, by system, by pipe size, and by pipe segments. LATS can generate an Excel GERP report that can be imported into the LG SOPS pricing and ordering system.

Proper Design to Install Procedure

LG encourages a two report design-to-install-procedure. After the design engineer determines building / zone loads and other details, the engineer opens the LATS program and inputs the project's information. When the design is complete, the "Auto Piping" and "System Check" functions must be used to verify piping sizes, limitations, and if any design errors are present. If errors are found, engineers must adjust the design, and run Auto Piping and System Check again. When the design passes the checks, then the engineer prints out a project "Shop Drawing" (LATS Tree Diagram) and provides it to the installing contractor. The contractor must follow the LATS Tree Diagram when building the piping system, but oftentimes the design changes on the building site:


- Architect has changed location and/or purpose of room(s).
- Outdoor unit cannot be placed where originally intended.
- Structural elements prevent routing the piping as planned.
- Air conditioning system conflicts with other building systems (plumbing, gas lines, etc.).

The contractor must mark any deviation from the design on the Shop Drawing, including as-built straight lines and elbows. This "Mark Up" drawing must be returned to the design engineer or Rep, who must input contractor changes into the LATS file. (Copy the original LATS software file, save and rename as a separate file, and modify all piping lengths by double-clicking on each length and editing information.) Like the shop drawing, the Auto Piping and System Check must also be run on this new "As Built" drawing. The design engineer or Rep must then provide the final As Built file to the contractor. The Mark Up version must be compared to the As Built version for the following:

- Differences in pipe diameter(s). If incorrect diameters have been installed, the piping must be changed out. If pipe diameters have changed, check to see if Y-Branches will also need to be changed.
- Changes to outdoor unit and indoor unit capacities. Capacities changes may impact line length changes.
- Additional refrigerant charge quantity ("Trim Charge"). Trim charge will change if piping lengths and diameters change. The As Built version must reflect installed piping lengths to ensure correct trim charge.

All documents submitted by the contractor, as well as the Shop Drawing and the As Built Drawing files must be provided for commissioning purposes. Model and serial numbers for all system components must also be submitted. If the steps previously detailed are not followed, and all documents are not provided to the LG Commissioner, the project runs the risk of not being commissioned and voiding any limited warranty LG offers on the equipment.

Figure 2: Example of a LATS Tree Diagram.



VERTICAL AIR HANDLING UNIT PRODUCT DATA

Mechanical Specifications on page 8

General Data on page 10

Electrical Data on page 16

Functions, Controls, and Options on page 17

Dimensions on page 19

Acoustic Data on page 23

Refrigerant Flow Diagrams on page 34

Wiring Diagrams on page 37

Electrical Connections on page 45

External Static Pressure and Airflow Ranges on page 52

Accessories on page 57

MECHANICAL SPECIFICATIONS

Casing

The unit is designed to operate in vertical up flow, down flow (requires conversion kit sold separately), horizontal left, and horizontal right configurations.

Supply air exits from the top and return air enters from the bottom for a vertical up flow configuration. Return air opening is from the top for the vertical down flow configuration. Return air opening is from right end or left end when in horizontal configuration.

The airflow circulation of the supply air and return air is reversed in a vertical down flow configuration. Return air plenum sub-base is to be field provided. Supply air opening has a male flange for duct connection.

The unit case is made of 22-gauge coated metal and the external surfaces are finished with a high gloss baked enamel finish. Finish color is "morning fog" (medium beige). Cold surfaces are galvanized steel.

The cold surfaces of the case are internally insulated with ½ inch foil faced, polystyrene fiber insulation. The inside surface of the fan assembly door access panel is treated with ½ inch polystyrene fiber insulation, encapsulated on both sides, and sealed along the edges with a reinforced foil-faced covering to prevent deterioration caused by panel removal.

All access panels are provided with gasket seals to minimize air leakage. The unit case is designed to accept an internal, optional, LG electric strip heater. The unit bears the CSA label. Unit breaker, fuses, and / or disconnect are provided by others.

Fan Assembly and Control

The indoor unit has an integral fan assembly consisting of a galvanized steel housing and a forward-curved fan wheel. The direct drive fan/motor assembly is mounted on rubber grommets isolating the rotating assembly from the fan housing.

The NJ (18k, 24k, 30k, and 36k) chassis is equipped with factory programmed ECM (Electronically Commutated Motor) to deliver constant CFM regardless of external static pressure. The fan motor for NK (42k, 48k, and 60k) is equipped with a Brushless Digitally-Controlled design (BLDC) fan motor, having permanently lubricated and sealed ball bearings. The fan motor includes thermal, overcurrent and low RPM protection.

The fan/motor assembly is mounted on vibration attenuating rubber grommets. The fan impeller is statically and dynamically balanced. Fan speed of NK chassis is controlled using a microprocessor-based direct digital control algorithm that provides a minimum of a high fan speed in cooling thermal ON and low fan speed in cooling thermal OFF, high fan speed in heating thermal ON and fan off in heating thermal OFF.

The fan speeds can be field adjusted between low, medium, and high speeds. DIP switch settings will allow the fan to run constantly during defrost or oil return modes.

No setting is required for NJ chassis; fan speed changes automatically to maintain programmed air flow settings as the static pressure changes. Each setting for NK chassis can be field adjusted from the factory setting (RPM/ESP).

Being a Constant Air Volume (CAV) unit, the NJ (18k, 24k, 30k, 36k) chassis does not require any field adjustment to change the ESP settings. The NK (42k, 48k, 60k) chassis comes with factory setting that provides delivery of air volume against an external static pressure of up to 1.0" in-wg.

Air Filter

The unit comes with a filter rack sized to hold a field-provided 16" x 20" x 1" (NJ frame) or 24" x 20" x 1" (NK frame) filter cartridge. The filter rack is equipped with guides that keep the filter centered in the rack. Filter service access is from the front of the unit without removing the coil or fan area access panels. Filter access door is provided with thumb screws that can be removed.

Optional Auxiliary Electric Heat Module(s)

LG optional electric heat modules are designed for field installation in the reheat position. The electric heat module is provided with heating elements, contactors, relays, high temperature safety switch, and interconnecting control wiring harness with a quick connect plug for easy connection to the unit control board. Auxiliary heat modules are available in nominal capacities of 3, 5, 8, 10, 15, and 20 kW.

The NJ chassis is compatible with the 3,5,8,10 kW auxiliary electric heaters and the NK chassis is compatible with the 3, 5, 8, 10, 15, 20 kW auxiliary electric heater.

Heating elements are powered from a field provided separate power source. 3kW through 10 kW modules are powered from a single power wire. The 15kW and 20 kW modules are powered from two power wires. Heating module breakers, fuses, and / or disconnects are to be field provided.

The optional electric heater when used with the provided simple controller or a 3rd party thermostat (via dry contact connection), will have automatic heating operation based on the internal logic. If manual heater operation is intended, an LG Programmable controller is required.

Microprocessor Control

The indoor unit is provided with an integrated control panel with built-in dry contact to communicate with the outdoor unit. All unit operation parameters are stored in non-volatile memory resident on the unit microprocessor. The microprocessor controls space temperature through using the value provided by temperature sensors within the indoor unit. A field-supplied communication cable must be installed to connect the indoor unit(s) to the outdoor unit.

MECHANICAL SPECIFICATIONS

Compressors

The 18,000 ~ 30,000, as well as the 42,000, 48,000, and 60,000 Btu/h outdoor units are equipped with one hermetically sealed, digitally controlled, inverter-driven twin rotary compressor to modulate capacity (modulation in 1 Hz increments).

The 36,000 Btu/h outdoor unit is equipped with one hermetically sealed, digitally controlled, inverter-driven scroll compressor to modulate capacity (modulation in 1 Hz increments).

Teflon coated bearings, overcurrent protection, and vibration isolation are integrated with the compressor.

Frequency ranges for the 18,000 ~ 30,000 Btu/h outdoor units are:

18 Btu/h = 15 to 80 Hz Cooling; 15 to 100 Hz Heating

24k Btu/h = 15 to 80 Hz Cooling; 15 to 100 Hz Heating

30k Btu/h = 15 to 80 Hz Cooling; 15 to 100 Hz Heating

Frequency ranges for the 36,000 ~ 60,000 Btu/h outdoor units are:

36k Btu/h = 10 to 120 Hz Cooling; 10 to 135 Hz Heating

42k Btu/h = 10 to 120 Hz Cooling; 10 to 135 Hz Heating

48K Btu/h = 10 to 120 Hz Cooling; 10 to 135 Hz Heating

60K Btu/h = 10 to 120 Hz Cooling; 10 to 135 Hz Heating

Controls

An LG wired controller can be used with the indoor unit, but is sold separately. Communication cable from the outdoor unit to the indoor unit must be a minimum of 14 AWG, four (4) conductor, shielded or unshielded (if shielded, must be grounded to chassis at ODU only) and must comply with applicable local and national codes.

The indoor unit has a built-in dry contact for a field supplied 3rd party thermostat. An optional Wi-Fi module is available as an additional accessory for use with LG's SmartThinQ app on a smart device.

Condensate

The unit is designed for gravity draining of condensate.

Condensate Drain Pan

The condensate drain pan is constructed of HIPS (high impact polystyrene resin).

Coil

The indoor unit coil is constructed with grooved design copper tubes with slit coil fins, 3 rows, 18 fins per inch. For 18k, 24k, and 30k outdoor units, there are 2 rows; for 36k, 42k, 48k, and 60k outdoor units, there are 3 rows. There are 18 fins per inch for all units.

Controls Features

- Inverter (Variable speed fan)
- Child lock function
- Auto changeover
- Auto restart operation
- Dehumidifying function
- Two thermistor control
- Group control
- External static pressure control
- Self-diagnostics function

Vertical Down Flow Configuration

NJ and NK frames come factory configured for vertical up flow. Down flow configuration requires a conversion kit sold separately (model numbers: PNDFJ0 for NJ frame and PNDFK0 for NK frame). The kit contains support brackets for the evaporator coil/drain pan subassembly, addition screws, and a replacement front panel to accommodate the coil and drain connections for down flow configuration.

Figure 3: Vertical Air Handling Unit System (LV181HV, LV241HV)



GENERAL DATA

Pairing Table

Table 1: Single Zone Vertical Air Handling Unit Pairing Table - NJ Frames

Outdoor Unit Model	Indoor Unit Model - NJ Frames
<p data-bbox="293 428 407 485">LUU180HV LUU240HV</p> 	<p data-bbox="776 428 906 537">LVN181HV4 LVN241HV4 LVN300HCV LVN361HV4</p> 
<p data-bbox="293 1037 407 1066">LUU360HV</p> 	

GENERAL DATA

Pairing Table

Table 2: Single Zone Vertical Air Handling Unit Pairing Table - NK Frames

Outdoor Unit Model	Indoor Unit Model - NK Frames
<p data-bbox="298 432 412 512">LUU420HV LUU480HV LUU601HV</p> 	<p data-bbox="786 432 899 512">LVN420HV LVN480HV LVN600HV</p> 

Product Data

GENERAL DATA / SPECIFICATIONS

Table 3: Vertical Air Handling Unit General Data - ODU and NJ Frame IDU.

Type	Vertical Air Handling Unit			
System Model (Indoor Unit / Outdoor Unit)	LV181HV (LVN181HV4/ LUU180HV)	LV241HV (LVN241HV4/ LUU240HV)	LV300HV (LVN300HCV/ LUU360HV)	LV361HV (LVN361HV4/ LUU360HV)
Cooling Capacity (Min / Rated / Max) (Btu/h)	7,200 ~ 18,000 ~ 24,000	9,600 ~ 23,200 ~ 30,000	12,000 ~ 30,000 ~ 32,500	14,400 ~ 33,200 ~ 39,000
Cooling Power Input ¹ (kW)	0.45 ~ 1.46 ~ 3.25	0.58 ~ 1.98 ~ 3.26	0.72 ~ 2.34 ~ 2.58	1.00 ~ 2.79 ~ 3.60
EER2 @95°F	12.30	11.70	12.80	11.90
SEER2	17.25	17.60	17	16.25
Heating Capacity (Min / Rated / Max) (Btu/h)	8,000 ~ 20,000 ~ 24,000	10,800 ~ 27,000 ~ 30,000	13,600 ~ 34,000 ~ 36,600	16,000 ~ 40,000 ~ 43,000
Heating Power Input ¹ (kW)	0.50 ~ 1.73 ~ 2.37	0.65 ~ 2.31 ~ 3.11	0.80 ~ 2.85 ~ 3.50	1.02 ~ 3.65 ~ 4.48
COP @47°F	3.4	3.42	3.5	3.21
HSPF2	9.25	9.70	9.2	8.95
<i>Maximum Heating Capacity (Btu/h)</i>				
Outdoor 17°F (DB) / Indoor 70°F (DB)	21,000	26,000	34,810	37,350
Outdoor 5°F (DB) / Indoor 70°F (DB)	16,200	21,400	32,600	33,800
Power Input [W] @ Outdoor 5°F (WB)	2,350	2,920	5,310	5,470
Outdoor -4 °F(DB) / Indoor 70°F (DB)	19,910	20,760	31,080	32,220
Power Supply V, Ø, Hz	208-230 / 1 / 60			
Power Wiring / Communications Cable (No. x AWG) ²	4 x 14			
<i>Outdoor Unit Operating Range</i>				
Cooling (°F DB)	5 to 118			
Optional Wind Baffle Cooling (°F DB)	Yes (-4)			
Heating (°F WB)	-4 to 64			
<i>Indoor Unit Operating Range</i>				
Cooling (°F WB)	57 to 77			
Heating (°F DB)	59 to 81			
<i>Indoor Temperature Setting Range</i>				
Cooling (°F DB)	65 to 86			
Heating (°F WB)	61 to 86			

EEV: Electronic Expansion Valve, IDU: Indoor Unit, ODU: Outdoor Unit. This unit comes with a dry helium charge.
 This data is rated 0 ft above sea level, with 24.6 ft of refrigerant line per indoor unit and a 0 ft level difference between outdoor and indoor units.
 Cooling capacity rating obtained with air entering the indoor coil at 80°F dry bulb (DB) and 67°F wet bulb (WB); and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).
 Heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB); and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

¹ Power Input is rated at high speed. Cooling range can be extended from 5°F down to -4°F using the Low Ambient Wind Baffle Kit (sold separately).

² All communication / connection (power) cable from the outdoor unit to the indoor unit are field supplied and is to be a minimum four-conductor, 14 AWG, stranded, shielded or unshielded (if shielded, it must be grounded to the chassis of ODU only), and must comply with applicable local and national codes.

³ Take appropriate actions at the end of HVAC equipment life to recover, recycle, reclaim or destroy R410A refrigerant according to applicable regulations (40 CFR Part 82, Subpart F) under section 608 of CAA.

⁴ Sound pressure levels are tested in an anechoic chamber under ISO Standard 3745 and are the same in both cooling and heating mode. These values can increase due to ambient conditions during operation.

⁵ Piping lengths are equivalent.

⁶ 18k and 24k VAHUs are supplied with socket adapters for pipe transitions.

GENERAL DATA / SPECIFICATIONS

Table 3: Vertical Air Handling Unit General Data - ODU and NJ Frame IDU, continued.

Type	Vertical Air Handling Unit			
System (Model) (Indoor Unit / Outdoor Unit)	LV181HV (LVN181HV4/ LUU180HV)	LV241HV (LVN241HV4/ LUU240HV)	LV300HV (LVN300HCV/ LUU360HV)	LV361HV (LVN361HV4/ LUU360HV)
<i>Unit Data</i>				
Refrigerant Type ³	R410A			
Additional Refrigerant Charge (oz./ft.)	0.43			
Refrigerant Control	EEV			
Indoor Unit Sound Pressure Level (dB(A)) (H/M/L) ⁴	35 / 33 / 30	36 / 34 / 30	44 / 41 / 39	44 / 41 / 39
Outdoor Unit Sound Pressure Level Max. (dB(A)) (Cool/Heat) ⁴	48 / 52	48 / 52	52 / 54	52 / 54
Indoor Unit Net / Shipping Weight (lbs.)	116.8 / 128.5	116.8 / 128.5	122.4 / 134.0	122.4 / 134.0
Outdoor Unit Net / Shipping Weight (lbs.)	130.1 / 147.7	130.1 / 147.7	193.1 / 217.4	193.1 / 217.4
Power Supply (No. x AWG)	3 x 12	3 x 12	3 x 10	3 x 10
Compressor (Type x Qty.)	Twin Rotary x 1	Twin Rotary x 1	Scroll x 1	Scroll x 1
Dehumidification Rate (pts./hr.)	4.2	4.0	5.1	5.1
<i>Fan</i>				
Indoor Unit Type x Qty.	Sirocco			
Outdoor Unit Type x Qty.	Propeller x 1	Propeller x 1	Propeller x 2	Propeller x 2
Motor / Drive	ECM (Electronically Commutated Motor)			
<i>Airflow Rate</i>				
Indoor Unit (H / M / L [CFM])	640 / 580 / 480	710 / 640 / 480	960 / 880 / 800	990 / 880 / 800
Outdoor Unit (CFM)	2,048	2,048	1,942 x 2	1,942 x 2
IDU ESP Range (Min ~ Default ~ Max) (in-wg)	Constant CFM @ 0.1 ~ ~ 0.7			
ODU Factory Set (High) External Static Pressure (in. wg)	0.1			
<i>Piping</i>				
ODU connection sizes (Liquid, Vapor) (in)	3/8 Flare, 5/8 Flare			
Installed pipe sizes (Liquid, Vapor) (in)	3/8 Flare, 5/8 Flare			
IDU connection sizes (Liquid, Vapor) (in) ⁶	3/8 Flare, 5/8 Flare			
Indoor Unit Condensate Drain O.D./I.D. (in.)	Primary & Secondary: 3/4 FPT			
Minimum / Maximum Pipe Length (ft.) ⁵	16.4 / 164	16.4 / 164	16.4 / 246	16.4 / 246
Piping Length (no additional refrigerant, ft.)	24.6			
Maximum Elevation Difference (ft.)	98.4			

EEV: Electronic Expansion Valve, IDU: Indoor Unit, ODU: Outdoor Unit. This unit comes with a dry helium charge.

This data is rated 0 ft above sea level, with 24.6 ft of refrigerant line per indoor unit and a 0 ft level difference between outdoor and indoor units.

Cooling capacity rating obtained with air entering the indoor coil at 80°F dry bulb (DB) and 67°F wet bulb (WB); and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB). Heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB); and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

1 Power Input is rated at high speed. Cooling range can be extended from 5°F down to -4°F using the Low Ambient Wind Baffle Kit (sold separately)

2 All communication / connection (power) cable from the outdoor unit to the indoor unit

are field supplied and is to be a minimum four-conductor, 14 AWG, stranded, shielded or unshielded (if shielded, it must be grounded to the chassis of ODU only), and must comply with applicable local and national codes.

3 Take appropriate actions at the end of HVAC equipment life to recover, recycle, reclaim or destroy R410A refrigerant according to applicable regulations (40 CFR Part 82, Subpart F) under section 608 of CAA.

4 Sound pressure levels are tested in an anechoic chamber under ISO Standard 3745 and are the same in both cooling and heating mode. These values can increase due to ambient conditions during operation.

5 Piping lengths are equivalent.

6 18k and 24k VAHUs are supplied with socket adapters for pipe transitions.

GENERAL DATA / SPECIFICATIONS

Table 4: Vertical Air Handling Unit General Data - ODU and NK Frame IDU.

Type	Vertical Air Handling Unit				
System Model (Indoor Unit / Outdoor Unit)	LV420HV1 (LVN420HV/ LUU420HV)	LV420HV2 (LVN420HV/ LUU601HV)	LV480HV1 (LVN480HV/ LUU480HV)	LV480HV2 (LVN480HV/ LUU601HV)	LV600HV (LVN600HV/ LUU601HV)
Cooling Capacity (Min / Rated / Max) (Btu/h)	17,000 ~ 42,000 ~ 48,000	17,000 ~ 42,000 ~ 48,000	18,000 ~ 48,000 ~ 53,000	18,000 ~ 46,000 ~ 53,000	20,500 ~ 52,500 ~ 60,500
Cooling Power Input ¹ (kW)	1.35 ~ 3.91 ~ 5.30	1.35 ~ 3.59 ~ 5.30	1.40 ~ 4.95 ~ 6.00	1.40 ~ 3.93 ~ 6.00	1.60 ~ 4.49 ~ 6.85
EER2 @95°F	11.90	11.70	9.70	11.70	11.70
SEER2	16.30	17.20	16.50	17.50	16.50
Heating Capacity (Min / Rated / Max) (Btu/h)	18,000 ~ 47,000 ~ 55,000	18,000 ~ 48,000 ~ 51,800	19,000 ~ 50,000 ~ 60,000	19,000 ~ 50,000 ~ 54,000	21,500 ~ 56,500 ~ 61,000
Heating Power Input ¹ (kW)	1.45 ~ 3.95 ~ 5.65	1.45 ~ 3.69 ~ 5.17	1.50 ~ 4.19 ~ 6.20	1.50 ~ 3.85 ~ 5.39	1.84 ~ 4.73 ~ 6.62
COP @47°F	3.49	3.81	3.50	3.81	3.50
HSPF2	9.35	9.30	9.30	9.20	9.20
<i>Maximum Heating Capacity (Btu/h)</i>					
Outdoor 17°F (DB) / Indoor 70°F (DB)	39,000	38,800	40,000	39,580	41,640
Outdoor 5°F (DB) / Indoor 70°F (DB)	38,500	40,000	39,500	40,500	41,500
Power Input [W] @ Outdoor 5°F (WB)	6,000	5,580	6,000	5,650	6,760
Outdoor -4 °F(DB) / Indoor 70°F (DB)	32,890	33,440	33,020	33,860	34,690
Power Supply V, Ø, Hz	208-230 / 1 / 60				
Power Wiring / Communications Cable (No. x AWG) ²	4 x 14				
<i>Outdoor Unit Operating Range</i>					
Cooling (°F DB)	5 to 118				
Optional Wind Baffle Cooling (°F DB)	Yes (-4)				
Heating (°F WB)	-4 to 64				
<i>Indoor Unit Operating Range</i>					
Cooling (°F WB)	57 to 77				
Heating (°F DB)	59 to 81				
<i>Indoor Temperature Setting Range</i>					
Cooling (°F DB)	65 to 86				
Heating (°F WB)	61 to 86				

EEV: Electronic Expansion Valve, IDU: Indoor Unit, ODU: Outdoor Unit. This unit comes with a dry helium charge.
 This data is rated 0 ft above sea level, with 24.6 ft of refrigerant line per indoor unit and a 0 ft level difference between outdoor and indoor units.
 Cooling capacity rating obtained with air entering the indoor coil at 80°F dry bulb (DB) and 67°F wet bulb (WB); and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).
 Heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB); and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

¹ Power Input is rated at high speed. Cooling range can be extended from 5°F down to -4°F using the Low Ambient Wind Baffle Kit (sold separately).

² All communication / connection (power) cable from the outdoor unit to the indoor unit are field supplied and is to be a minimum four-conductor, 14 AWG, stranded, shielded or unshielded (if shielded, it must be grounded to the chassis of ODU only), and must comply with applicable local and national codes.
³ Take appropriate actions at the end of HVAC equipment life to recover, recycle, reclaim or destroy R410A refrigerant according to applicable regulations (40 CFR Part 82, Subpart F) under section 608 of CAA.
⁴ Sound pressure levels are tested in an anechoic chamber under ISO Standard 3745 and are the same in both cooling and heating mode. These values can increase due to ambient conditions during operation.
⁵ Piping lengths are equivalent.
⁶ 18k and 24k VAHUs are supplied with socket adapters for pipe transitions.

GENERAL DATA / SPECIFICATIONS

Table 4: Vertical Air Handling Unit General Data - ODU and NK Frame IDU, continued.

Type	Vertical Air Handling Unit				
System (Model) (Indoor Unit / Outdoor Unit)	LV420HV1 (LVN420HV/ LUU420HV)	LV420HV2 (LVN420HV/ LUU601HV)	LV480HV1 (LVN480HV/ LUU480HV)	LV480HV2 (LVN480HV/ LUU601HV)	LV600HV (LVN600HV/ LUU601HV)
Unit Data					
Refrigerant Type ³	R410A				
Additional Refrigerant Charge (oz./ft.)	0.43				
Refrigerant Control	EEV				
Indoor Unit Sound Pressure Level (dB(A)) (H/M/L) ⁴	48 / 45 / 44	48 / 45 / 44	49 / 48 / 44	49 / 48 / 44	50 / 49 / 48
Outdoor Unit Sound Pressure Level Max. (dB(A)) (Cool/Heat) ⁴	52 / 54	52 / 54	52 / 54	52 / 54	52 / 54
Indoor Unit Net / Shipping Weight (lbs.)	158.7 / 176.4	158.7 / 176.4	158.7 / 176.4	158.7 / 176.4	158.7 / 176.4
Outdoor Unit Net / Shipping Weight (lbs.)	193.1 / 217.4	210.8 / 234.6	193.1 / 217.4	210.8 / 234.6	210.8 / 234.6
Power Supply (No. x AWG)	3 x 10	3 x 10	3 x 10	3 x 10	3 x 10
Compressor (Type x Qty.)	Scroll x 1	R1 Scroll x 1	Scroll x 1	R1 Scroll x 1	R1 Scroll x 1
Dehumidification Rate (pts./hr.)	9.1	9.1	11.0	11.0	12.0
Fan					
Indoor Unit Type x Qty.	Sirocco x 1				
Outdoor Unit Type x Qty.	Propeller x 2				
Motor / Drive	Brushless Digitally Controlled / Direct				
Airflow Rate					
Indoor Unit (H / M / L [CFM])	1,260 / 1,100 / 1,000	1,260 / 1,100 / 1,000	1,400 / 1,260 / 1,000	1,400 / 1,260 / 1,000	1,475 / 1,400 / 1,260
Outdoor Unit (CFM)	1,942 x 2				
IDU ESP Range (Min ~ Default ~ Max) (in-wg)	0.1 ~ 0.3 ~ 1.0				
ODU Factory Set (High) ESP (in. wg)	0.1				
Piping					
ODU connection sizes (Liquid, Vapor) (in)	3/8 Flare, 5/8 Flare	3/8 Flare, 3/4 Flare	3/8 Flare, 5/8 Flare	3/8 Flare, 3/4 Flare	3/8 Flare, 3/4 Flare
Installed pipe sizes (Liquid, Vapor) (in)	3/8 Flare, 5/8 Flare	3/8 Flare, 5/8 Flare	3/8 Flare, 5/8 Flare	3/8 Flare, 5/8 Flare	3/8 Flare, 3/4 Flare
IDU connection sizes (Liquid, Vapor) (in) ⁶	3/8 Flare, 5/8 Flare	3/8 Flare, 5/8 Flare	3/8 Flare, 5/8 Flare	3/8 Flare, 5/8 Flare	3/8 Flare, 3/4 Flare
Indoor Unit Condensate Drain O.D./I.D. (in.)	Primary & Secondary: 3/4 FPT				
Minimum / Maximum Pipe Length (ft.) ⁵	16.4 / 246				
Piping Length (no additional refrigerant, ft.)	24.6				
Maximum Elevation Difference (ft.)	98.4				

EEV: Electronic Expansion Valve, IDU: Indoor Unit, ODU: Outdoor Unit. This unit comes with a dry helium charge.
 This data is rated 0 ft above sea level, with 24.6 ft of refrigerant line per indoor unit and a 0 ft level difference between outdoor and indoor units.
 Cooling capacity rating obtained with air entering the indoor coil at 80°F dry bulb (DB) and 67°F wet bulb (WB); and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).
 Heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB); and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).
 1 Power Input is rated at high speed. Cooling range can be extended from 5°F down to -4°F using the Low Ambient Wind Baffle Kit (sold separately)
 2 All communication / connection (power) cable from the outdoor unit to the indoor unit

are field supplied and is to be a minimum four-conductor, 14 AWG, stranded, shielded or unshielded (if shielded, it must be grounded to the chassis of ODU only), and must comply with applicable local and national codes.
 3 Take appropriate actions at the end of HVAC equipment life to recover, recycle, reclaim or destroy R410A refrigerant according to applicable regulations (40 CFR Part 82, Subpart F) under section 608 of CAA.
 4 Sound pressure levels are tested in an anechoic chamber under ISO Standard 3745 and are the same in both cooling and heating mode. These values can increase due to ambient conditions during operation.
 5 Piping lengths are equivalent.
 6 18k and 24k VAHUs are supplied with socket adapters for pipe transitions.

ELECTRICAL DATA

Electrical Data

Table 5: Vertical Air Handling Unit ODU Electrical Data.

Nominal Tons	Model Name	Unit			Power Supply		Compressor Quantity	Compressor Motor RLA (Cooling)	Condenser Fan Motor(s)	
		Hz	Volts	Voltage Range	MCA	MOP			Condenser Fan Quantity.	Condenser Fan Motor FLA
1.5	LUU180HV	60	208/230	Min.: 187 Max.: 253	20	30	1	13.5	1	1.6
2.0	LUU240HV				20	30	1	13.5	1	1.6
3.0	LUU360HV				32	40	1	22.0	2	1.6 x 2
3.5	LUU420HV				32	40	1	22.0	2	1.6 x 2
4.0	LUU480HV				32	40	1	22.0	2	1.6 x 2
5.0	LUU601HV				32	40	1	22.0	2	1.6 x 2

Voltage tolerance is $\pm 10\%$.

Maximum allowable voltage unbalance is 2%.

RLA = Rated Load Amps.

MCA = Minimum Circuit Ampacity.

Maximum Overcurrent Protection (MOP) is calculated as follows:

(Largest motor FLA x 2.25) + (Sum of other motor FLA) rounded down to the nearest standard fuse size.

FUNCTIONS, CONTROLS, AND OPTIONS

Indoor Unit

Functions, Controls, and Options for LVN181HV4, LVN241HV4, LVN300HCV, LVN361HV4, LVN420HV, LVN480HV, LVN600HV

Table 6: Indoor Unit—Functions, Controls and Options.

Indoor Unit Type		Vertical Air Handling Unit
Airflow	Air Supply Outlet	1
	Airflow steps (fan/cool/heat)	3/3/3
	Washable anti-fungal filter ¹	X
Operation	Drain pump	X
	E.S.P (External Static Pressure) Control (NK Chassis Frames)	√
	Hot Start	√
	Self diagnostics	√
	Soft Dry (dehumidification)	√
	Auto changeover	√
	Auto restart	√
	Child lock	o
	Sleep mode	√
	Timer (on/off)	√
	Weekly schedule	√
	Two thermistor control	o
Controllers	7-Day programmable controller	o
	Simple wired remote controller	o
	Wireless LCD remote control ²	o
	Dry contact	√
	Dry contact (temperature setting)	X
	Central control (LGAP)	√
Special Functions	Wi-Fi ³	o
	Auxiliary Heater Relay Kit (PRARH1)	o

¹Primary washable filters.

²Requires wired zone controller.

³Requires Wi-Fi module PWFMD200.

√ = Standard feature

o = Unit option

X = Not Available

FUNCTIONS, CONTROLS, AND OPTIONS

Outdoor Unit

Functions, Controls, and Options for LUU180HV, LUU240HV, LUU360HV, LUU420HV, LUU480HV, LUU601HV

Table 7: Outdoor Unit—Functions, Controls and Options.

Outdoor Unit							
Category	Functions	LUU180HV	LUU240HV	LUU360HV	LUU420HV	LUU480HV	LUU601HV
Reliability	Defrost / Deicing	O	O	O	O	O	O
	High pressure sensor	O	O	O	O	O	O
	Phase protection	X	X	X	X	X	X
	Restart delay (3-minutes)	O	O	O	O	O	O
	Self diagnosis	O	O	O	O	O	O
	Soft start	O	O	O	O	O	O
Convenience	Night Quiet Operation	O	O	O	O	O	O
	Mode Lock	O	O	O	O	O	O
	Pump Down (Forced Cooling Operation)	O	O	O	O	O	O
	Network solution (LGAP)	O	O	O	O	O	O
Central Controller	AC Smart 5	PACS5A000	PACS5A000	PACS5A000	PACS5A000	PACS5A000	PACS5A000
	ACP 5	PACP5A000	PACP5A000	PACP5A000	PACP5A000	PACP5A000	PACP5A000
	PI485	PMNFP14A1	PMNFP14A1	PMNFP14A1	PMNFP14A1	PMNFP14A1	PMNFP14A1
Remote Controller	MultiSITE CRC2	PREMTBVC2	PREMTBVC2	PREMTBVC2	PREMTBVC2	PREMTBVC2	PREMTBVC2
	MultiSITE CRC2+	PREMTBVC3	PREMTBVC3	PREMTBVC3	PREMTBVC3	PREMTBVC3	PREMTBVC3
	MultiSITE CRC2+Z	PREMTBVC4	PREMTBVC4	PREMTBVC4	PREMTBVC4	PREMTBVC4	PREMTBVC4
Integration Solution	MultiSITE Communications Manager	PBACNBTR0A	PBACNBTR0A	PBACNBTR0A	PBACNBTR0A	PBACNBTR0A	PBACNBTR0A

√ = Standard feature

O = Unit option


X = Not Available

OUTDOOR UNIT DIMENSIONS

LUU180HV, LUU240HV

Dimensions for LUU180HV, LUU240HV

Figure 4: LUU180HV, LUU240HV Unit Dimensions.




OUTDOOR UNIT DIMENSIONS

LUU360HV, LUU420HV, LUU480HV, LUU601HV

Dimensions for LUU360HV, LUU420HV, LUU480HV, LUU601HV

Figure 5: LUU360HV, LUU420HV, LUU480HV, LUU601HV Unit Dimensions.







INDOOR UNIT DIMENSIONS

LVN181HV4, LVN241HV4, LVN300HCV, LVN361HV4

Dimensions for LVN181HV4, LVN241HV4, LVN300HCV, LVN361HV4 (NJ Chassis)

Figure 6: LVN181HV4, LVN241HV4, LVN300HCV, LVN361HV4 Indoor Unit Dimensions.




ACOUSTIC DATA

Indoor Units Sound Pressure

Indoor Unit Sound Pressure Measurement

Figure 8: Sound Pressure Measurement Location.



- Measurements are taken 3.3 ft away from the front of the unit.
- Sound pressure levels are measured in dB(A) with a tolerance of ± 1 .
- Sound pressure levels are tested in an anechoic chamber under ISO Standard 3745.

Operating Conditions:

- Power source: 220V/60 Hz
- Sound level will vary depending on a range of factors including the construction (acoustic absorption coefficient) of a particular room in which the unit was installed.

Indoor Unit Sound Pressure Levels

Table 8: Vertical Air Handling Unit Indoor Unit Sound Pressure Levels.

Model	Sound Pressure Levels dB(A)		
	High Fan Speed	Medium Fan Speed	Low Fan Speed
LVN181HV4	35	33	30
LVN241HV4	36	34	30
LVN300HCV	44	41	39
LVN361HV4	44	41	39
LVN420HV	48	45	44
LVN480HV	49	48	44
LVN600HV	50	49	48

ACOUSTIC DATA

Indoor Units Sound Pressure

Sound Pressure Diagrams for LVN181HV4, LVN241HV4, LVN300HCV, LVN361HV4

Figure 9: LVN181HV4 Sound Pressure Level Diagram.

LVN181HV4




Figure 10: LVN241HV4 Sound Pressure Level Diagram.

LVN241HV4




Figure 11: LVN300HCV Sound Pressure Level Diagram.

LVN300HCV





Figure 12: LVN361HV4 Sound Pressure Level Diagram.

LVN361HV4



ACOUSTIC DATA

Indoor Units Sound Pressure

Sound Pressure Diagrams for LVN420HV, LVN480HV, LVN600HV

Figure 13: LVN420HV Sound Pressure Level Diagram.




Figure 14: LVN480HV Sound Pressure Level Diagram.





Figure 15: LVN600HV Sound Pressure Level Diagram.



ACOUSTIC DATA

Indoor Units Sound Power

Sound Power Levels

Table 9: Vertical Air Handling Unit Sound Power Levels.



Indoor Unit Model	Sound Power Levels dB(A)
	High Fan Speed
LVN181HV4	54
LVN241HV4	55
LVN361HV4	63
LVN420HV	61
LVN480HV	62
LVN600HV	63

- Data is valid under diffuse field conditions.
- Data is valid under nominal operating conditions.
- Sound power level is measured using rated conditions, and tested in a reverberation room per ISO 3741 standards.
- Sound level will vary depending on a range of factors such as construction (acoustic absorption coefficient) of particular area in which the equipment is installed.
- Reference acoustic intensity: 0dB = 10E-6μW/m²

Sound Power Level Diagrams for LVN181HV4, LVN241HV4

Figure 16: LVN181HV4 Sound Power Level Diagram.

Figure 17: LVN241HV4 Sound Power Level Diagram.



Sound Power Level Diagrams for LVN300HCV, LVN361HV4

Figure 18: LVN300HCV Sound Power Level Diagram.
LVN300HCV





Figure 19: LVN361HV4 Sound Pressure Level Diagram.
LVN361HV4



ACOUSTIC DATA

Indoor Units Sound Power

Sound Power Level Diagrams for LVN420HV, LVN480HV, LVN600HV

Figure 20: LVN420HV Sound Power Level Diagram.




Figure 21: LVN480HV Sound Power Level Diagram.






Figure 22: LVN600HV Sound Power Level Diagram.



Outdoor Unit Sound Pressure Level Measurement

Figure 23: Vertical Air Handling Unit Outdoor Unit Sound Pressure Level Measurement Location.



- Measurements taken with no attenuation and units operating at full load normal operating condition.
- Sound level will vary depending on a range of factors such as construction (acoustic absorption coefficient) of particular area in which the equipment is installed.
- Sound power levels are measured in dB(A)±1.
- Tested in anechoic chamber per ISO Standard 3745.

Outdoor Unit Sound Pressure Levels

Table 10: Vertical Air Handling Unit Outdoor Unit Sound Pressure Levels (dB[A]).

Outdoor Unit Model	Sound Pressure Level [dB(A)]	
	Cooling	Heating
LUU180HV	48	52
LUU240HV	48	52
LUU360HV	52	54
LUU420HV	52	54
LUU480HV	52	54
LUU601HV	54	56

ACOUSTIC DATA

Outdoor Units Sound Pressure

Sound Pressure Diagrams for LUU180HV, LUU240HV, LUU360HV, LUU420HV, LUU480HV

Figure 24: LUU180HV, LUU240HV Sound Pressure Level Diagram.




Figure 25: LUU360HV Sound Pressure Level Diagram.




Figure 26: LUU420HV, LUU480HV Sound Pressure Level Diagram.





Figure 27: LUU601 Sound Pressure Level Diagram.



ACOUSTIC DATA

Outdoor Units Sound Power

Outdoor Unit Sound Power Levels


Table 11: Vertical Air Handling Unit ODU Sound Power Levels.

Outdoor Unit Model	Sound Power Levels dB(A)
	Max
LUU180HV	67
LUU240HV	67
LUU360HV	65
LUU420HV	67
LUU480HV	68
LUU601HV	71

Sound Power Level Diagram for LUU180HV, LUU240HV

Figure 28: LUU180HV, LUU240HV Sound Power Level Diagram.

LUU180HV, LUU240HV



ACOUSTIC DATA

Outdoor Units Sound Power

Sound Power Level Diagram for LUU360HV, LUU420HV

Figure 29: LUU360HV Sound Power Level Diagram.
LUU360HV





Figure 30: LUU360HV Sound Power Level Diagram.
LUU420HV



Sound Power Level Diagrams for LUU480HV, LUU601HV

Figure 31: LUU480HV Sound Power Level Diagram.
LUU480HV





Figure 32: LUU480HV Sound Power Level Diagram.
LUU601HV



REFRIGERANT FLOW DIAGRAM

Indoor Units

Refrigerant Flow Diagram for LVN181HV4, LVN241HV4, LVN300HCV, LVN361HV4, LVN420HV, LVN480HV, LVN600HV

Figure 33: Indoor Unit Refrigerant Flow Diagrams.




Table 12: Refrigerant Pipe Connection Port Diameters.

Indoor Unit Model	Liquid (inch)	Vapor (inch)
<i>NJ Frames</i>		
LVN181HV4	3/8	5/8
LVN241HV4		
LVN300HCV		
LVN361HV4		
<i>NK Frames</i>		
LVN420HV	3/8	5/8
LVN480HV		
LVN600HV	3/8	3/4

Table 13: Refrigerant Pipe Sizes.


Indoor Unit Model	Liquid (inch)	Vapor (inch)
<i>NJ Frames</i>		
LVN181HV4	3/8	5/8
LVN241HV4		
LVN300HCV		
LVN361HV4		
<i>NK Frames</i>		
LVN420HV	3/8	5/8
LVN480HV		
LVN600HV	3/8	3/4

REFRIGERANT FLOW DIAGRAM

Outdoor Units

Refrigerant Flow Diagram for LUU180HV, LUU240HV, LUU360HV, LUU420HV, LUU480HV

Figure 34: LUU180HV, LUU240HV, LUU360HV, LUU420HV, LUU480HV Refrigerant Flow Diagrams.



Product Data

Table 14: Vertical Air Handling Unit ODU LUU180~480HV Thermistor Details.

Description	PCB Connector
Suction Temperature Thermistor	CN_SUCTION_GR
Discharge Temperature Thermistor	CN_DISCHA_BK
Condenser Out Temperature Thermistor	CN_C_PIPE_VI
Outdoor Ambient Air Temperature Thermistor	CN_AIR_YL
Condensing Temperature Thermistor	CN_MID_BR
Pressure Sensor	CN_H_PRESS_RD

REFRIGERANT FLOW DIAGRAM

Outdoor Units

Refrigerant Flow Diagram for LUU601HV

Figure 35: LUU601 Refrigerant Flow Diagram.





Table 15: Vertical Air Handling Unit ODU LUU601HV Thermistor Details.

Description	PCB Connector
Discharge Pipe Temperature	CN_DISCHA_BK
Suction Pipe Temperature	CN_SUCTION_GR
Condenser Out Pipe Temperature	CN_C_PIPE_VI
Air Temperature	CN_AIR_YL
Condenser Mid Pipe Temperature	CN_MID_BR
Vapor Injection In Temperature	CN_VI_IN_WH
Vapor Injection Out Temperature	CN_VI_OUT_BL
Pressure	CN_H_PRESS_RD

INDOOR UNIT WIRING DIAGRAM

Wiring Diagram for LVN181HV4, LVN241HV4, LVN300HCV, LVN361HV4

Figure 36: Indoor Unit Wiring Diagram.




Product Data

INDOOR UNIT WIRING DIAGRAM

Wiring Diagram for LVN420HV, LVN480HV


Figure 37: Indoor Unit Wiring Diagram.



INDOOR UNIT WIRING DIAGRAM

Wiring Diagram for LVN600HV

Figure 38: Indoor Unit Wiring Diagram.




Product Data

OUTDOOR UNIT WIRING DIAGRAM

Wiring Diagram for LUU180HV, LUU240HV


Figure 39: Outdoor Unit Wiring Diagram.



OUTDOOR UNIT WIRING DIAGRAM

Wiring Diagram for LUU360HV, LUU420HV, LUU480HV

Figure 40: LUU360HV, LUU420HV, LUU480HV Outdoor Unit Wiring Diagram.



ELECTRICAL WIRING

NJ / NK Frame Wiring Diagram Legend

Table 16: NJ/NK Frame Wiring Diagram Legend.

Terminal	Purpose	Function
CN-POWER	AC Power supply	AC Power line
CN-MOTOR1	Fan motor output	Motor output of BLDC
CN_OUT	Heater	Connection for heater
CN-D/PUMP	Drain pump output	AC output for drain pump
CN-FLOAT	Float switch input	Float switch sensing
CN-ZONE	Zone controller	Zone controller connection
CN-OPTION	Optional PCB EPROM	Option PCB connection
CN-EXT	External ON / OFF controller	External ON / OFF controller connection
CN-DISPLAY	Display	Display of indoor status
CN-CC	Dry contact	Dry Contact connection
CN-PIPE/OUT (RD)	Discharge pipe sensor	Pipe out thermistor
CN-LEAK (VI)	Refrigerant leak detector	Refrigerant leak detector connection
CN-PIPE/IN (WH)	Suction pipe sensor	Pipe in thermistor
CN-REMO (GN)	Wired remote controller	Wired remote control connection
CN-ROOM (YL)	Room sensor	Room air thermistor
CN-DAMPER	Damper Controller	Damper connection
CN-AIRC	Air Cleaner	Air Cleaner connection
CN-WF	Wifi	Wifi Module connection
CN-PTC	Auxiliary Heater Relay Kit	Auxiliary Heater Relay Kit Second stage heat

ELECTRICAL WIRING

DIP Switch Settings

DIP Switch Settings for Indoor Unit PCB

Table 17: NJ/NK Frame DIP Switch Settings.

Dip Switch	Function	Off	On	Description
SW1	COMMUNICATION	Off (default)	–	–
SW2	CYCLE	Off (default)	–	–
SW3	GROUP CONTROL	Master	Slave	Group control setting using 7-Day Programmable Controller; selects Master/Slave on each indoor unit.
SW4	DRY CONTACT MODE	Variable	Auto	Sets operation mode for optional Dry Contact accessory. 1. Variable: Auto or Manual Mode can be set through 7-Day Programmable Controller or Wireless Remote Controller (factory default setting is Auto if there is no setting). 2. Auto: For Dry Contact, it is always Auto mode.
SW5	CONTINUOUS FAN	Off	On	Selects continuous fan for ducted indoor units. 1. On: Indoor unit fan will always operate at a set fan speed, except when the system is off, or the outdoor unit is in defrost mode (when the outdoor unit is in defrost mode, the fan will operate at super low fan speed). 2. Off: Indoor unit fan speed can be changed by on / off.
SW6	HEATER INTERLOCK	Off	On	Selects heater interlock function for Vertical Air Handling units. 1. On: Automatic (heater will automatically operate during heating mode). 2. Off: Manual (heater needs to be manually turned on during heating mode).
SW7				Off
SW8				Off

Note:

To operate the indoor unit without Internal Electric Heater, Dip switch 1, 2, 6, 8 must be set OFF.

To operate the indoor unit with Internal Electric heater, Dip switch 6 must be set ON.

- SW6 ON: Automatic Heater operation: Heater operates automatically.
- SW6 OFF: Manual Heater operation: Owner's involvement is required for on/off operation.

If you operate the indoor unit with Internal Electric heater with Dip switch 5, note the following:

- SW5 ON: Fan operates continuously. During defrosting or oil return operation, uninterrupted heating can be attained, as a result of continuous heater and fan operation.
- SW5 OFF: Fan discontinuous operation. There would be reduction in heating capacity while defrosting or oil return operation.

ELECTRICAL CONNECTIONS

General Power Wiring / Communications Cable Guidelines

- Follow manufacturer's circuit diagrams displayed on the inside of the control box cover.
- Have a separate power supply for the indoor units.
- Provide a circuit breaker switch between the power source and the indoor unit.
- Confirm power source specifications.
- Properly ground the outdoor unit and the indoor unit per NEC and local codes.
- Connect the wiring firmly so that the wires cannot be easily pulled out.
- Confirm that the electrical capacity is sufficient.
- Power supply to the outdoor unit must be selected based on NEC and local codes. Maximum allowable voltage fluctuation $\pm 10\%$ or name-plate rated value.
- It is recommended that a circuit breaker is installed, especially if conditions could become wet or moist.
- Include a disconnect in the power wiring system. Add an air gap contact separation of at least 1/8 inch in each active (phase) conductor.
- Any openings where the field wiring enters the cabinet must be completely sealed.

⊘ Do not install power wiring to the outdoor unit and the communication / connection (power) cable to the indoor unit in the same conduit. Use separate conduits.

Power Wiring / Communications Cable Specifications

- Power wiring to the outdoor unit must be solid or stranded, and must comply with the applicable local and national electric codes.
- Communication cable from the outdoor unit to the indoor unit must be a minimum of 14 AWG, four (4) conductor, shielded or unshielded (if shielded, must be grounded to chassis at ODU only) and must comply with applicable local and national codes.
- Communication cable from indoor unit to remote controller(s) is to be 22 AWG, 3-conductor, twisted, stranded, unshielded. Wiring must comply with all applicable local and national codes.

WARNING

- Terminal screws may become loose during transport. Properly tighten the terminal connections during installation or risk electric shock, physical injury, or death.
- Loose wiring may cause unit to malfunction, overheat, and catch fire, resulting in severe injury or death.

Note:


- Terminal screws may loosen during transport. Properly tighten the terminal connections during installation or risk equipment malfunction or property damage.
 - Loose wiring may cause unit malfunction, the wires to burnout or the terminal to overheat and catch fire. There is a risk of equipment malfunction or property damage.
- A voltage drop may cause the following problems:
- Magnetic switch vibration, fuse breaks, or disturbance to the normal function of an overload protection device.
 - Compressor will not receive the proper starting current.

ELECTRICAL CONNECTIONS

Note:

- Always verify the communication cable is connected to a communications terminal on the Single Zone unit. Ⓣ Never apply line voltage power to the communication cable connection. If contact is made, the PCBs will be damaged.
- The shield of the communications cable connecting the outdoor unit to the indoor unit must be grounded only to the outdoor unit frame.
- Tie the shield of each cable segment together using a wire nut at the indoor unit. Maintain polarity throughout the communication network.
- Position the incoming power to the outdoor unit away from the power / communications cables from the outdoor unit to the indoor unit.
- Ⓣ Never use a common multiple-core communications cable.

Figure 42: Typical Single Zone Outdoor Unit to Indoor Unit Wiring and Communications Cable Diagram.



⚠ WARNING

All power wiring and communication cable installation must be performed by trained service providers working in accordance with local, state, and National Electrical Code (NEC) / UL / ETL federal regulations related to electrical equipment and wiring, and following the manufacturer product diagrams, requirements, and instructions in this manual. Failure to do so will lead to electric shock which can cause physical injury or death.

ELECTRICAL CONNECTIONS

Figure 43: LV181HV and LV241HV General Power/Communications System Schematic.





Figure 44: LV300HV, LV361HV, LV420HV1, LV420HV2, LV480HV1, LV480HV2, and LV600HV General Power/Communications System Schematic.



Note:

- Secure the separate wires in the control box panel using zip ties.
- Secure wiring with accessory clamps so that it does not touch the piping.
- Use a conduit for the communications cable / power wiring from the outdoor unit to the indoor units.
- Make sure the communications cable / power wiring from the outdoor units to the indoor units, and the power wiring to the outdoor unit are separate, otherwise, the outdoor unit operation may be affected by electrical noise and will malfunction or fail.

ELECTRICAL CONNECTIONS

Connections and Specifications

Communication / Connection (Power) Cable Specifications from Outdoor Unit to Indoor Unit

- For communication / connection (power) wires between the Single Zone outdoor unit and the indoor unit, use a minimum 14 gauge, four (4) conductor, stranded, shielded or unshielded wire. If shielded, the wire must be grounded to the chassis at the outdoor unit only.
- Insulation material as required by local code.
- Firmly attach the cable; provide slack but secure in a way to prevent external forces from being imparted on the terminal block.
- Wiring must be completed without splices.

Note:

- *Use of 14 gauge, four (4) conductor, stranded, shielded or unshielded wire is allowed for lengths up to the published maximum pipe length, plus recommended slack at both ends.*

ELECTRICAL CONNECTIONS

Connecting the Power Wiring and Communications Cable

1. To access the terminal block, first unscrew the top front panel, and then unscrew the cover from the control box.
2. Knockout the access holes for the wiring. Insert the power wiring/communications cable from the outdoor unit through the conduits, pass the conduits through the designated access holes, and then insert the conduits into the control box. To prevent electromagnetic interference and product malfunction, leave a space between the power wiring and communications cable outside of the indoor unit.
3. Connect the power wiring and communications cables to the appropriate terminals on the indoor unit control board. Verify that the color and terminal numbers from the outdoor unit wiring match the color and terminal numbers on the indoor unit.
4. Fill in any gaps around the conduit access holes with sealant to prevent foreign particles from entering the indoor unit.

Figure 45: Connecting the Power Wiring and Communications Cable.





Figure 46: Indoor Unit to Outdoor Unit Power Wiring / Communications Cable Connections.



ELECTRICAL CONNECTIONS

Controller Options

Optional LG-supplied wired controller or wireless handheld controllers are available to be used with the Vertical Air Handling indoor units.

Wireless Handheld Remote Controller features

- Operation Display Panel: Displays operation conditions.
- Temperature Control Button: Sets desired temperature.
- Fan Speed Button: Sets desired fan speed.
- On / Off Button: Turns system operation on and off.
- Mode Selection Check Button: Selects the operation mode: Cooling, Heating, Auto, Dry (Dehumidification), or Fan.

Note:

Each function will display on the LED for about three (3) seconds when the power is first cycled on.

Wired Controller Connections

Controllers can connect to the indoor unit in one of two different ways.

1. LG Wired Remote Extension Cable with Molex plug (PZCWRC1; sold separately) that connects to the CN-REMO terminal on the indoor unit PCB.
2. Field-supplied controller cable that connects to the indoor unit terminal block (must be at least UL2547 or UL1007, and at least FT-6 rated if local electric and building codes require plenum cable usage). Communication cable from indoor unit to remote controller(s) is to be 22 AWG, 3-conductor, twisted, stranded, unshielded. Wiring must comply with all applicable local and national codes.

Figure 47: PZCWRC1 LG Wired Remote Extension Cable.





Figure 48: Wired Controller Connection on the Indoor Unit Terminal Block.



Note:

When using field-supplied controller cable, make sure to connect the yellow to yellow (communications wire), red to red (12V power wire), and black to black (ground wire) terminals from the remote controller to the indoor unit terminal blocks.

ELECTRICAL CONNECTIONS

Wired Controller Placement

Wired controllers include a sensor to detect room temperature. To maintain comfort levels in the conditioned space, the wired controller must be installed in a location away from direct sunlight, high humidity, and where it could be directly exposed to cold air. Controller must be installed four (4) to five (5) feet above the floor where its LED display can be read easily, in an area with good air circulation, and where it can detect an average room temperature.

⊘ Do not install the wired controller near or in:

- Drafts or dead spots behind doors and in corners
- Hot or cold air from ducts
- Radiant heat from the sun or appliances
- Concealed pipes and chimneys
- An area where temperatures are uncontrolled, such as an outside wall

Hanging the Wired Controller

1. The controller wiring / cable can be installed in one of three directions: top, back, or on the right side. If top or right side installation is desired, remove cable guide grooves on the controller, and then position wiring / cable on applicable side.
2. Choose and mark the area of installation, and then screw the wall plate into place (using the provided parts). Install the controller wall plate to fit the electrical box if one is present. Ensure that no gaps exist between the wall plate and the wall itself.
3. Arrange wiring / cables so as not to interfere with the controller circuitry. Position the wired controller on the wall plate. Snap into place by pressing the bottom part of the wired controller onto the wall plate. Make sure that no gaps exist between the wired controller and the wall plate on all sides.
4. To remove wired controller from the wall plate, insert a screwdriver into the two holes at the bottom. Twist screwdriver to release controller. ⊘ Do not damage the controller components when removing.

Assigning the Thermistor for Temperature Detection

Each indoor unit includes a return air thermistor assigned to sense the temperature. If a wired controller is installed, there is a choice of sensing temperature with either the indoor unit return air thermistor or the thermistor in the wired controller. It is also an option to set both thermistors to sense temperature so that indoor unit bases its operation on the first thermistor to reach the designated temperature differential. For applicable indoor units, an optional Remote Temperature Sensor can be used in lieu of the return air thermistor—either alone or in conjunction with a wired controller thermistor as previously described.

Figure 49: Proper Location for the Wired Controller.




Figure 50: Removing the Cable Guide Grooves.




Figure 51: Attaching the Wall Plate.





Figure 52: Installing / Removing the Controller.



EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES

External Static Pressure (ESP) Default Settings (NJ frame)


Table 18: ESP Setting Values (NJ frame).

Model Number	Air Volume*		
	High	Medium	Low
LVN181HV4	640	580	480
LVN241HV4	710	640	480
LVN300HCV	960	880	800
LVN361HV4	990	880	800

*Installer settings available to change the CFM to 10% above or 10% below the values mentioned in the above table.

External Static Pressure Setting Values (NK frame)

Figure 53: ESP Setting Values (NK frame).



EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES

IDU External Static Pressure Setting Values

Table 19: Vertical Air Handling Unit Indoor Unit External Static Pressure and Air Flow Tables.

Static Pressure (in. wg)			0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1
Model No. / Nominal Capacity of System (Btu/h)	Airflow Rate / CFM		Setting Value (in. WG) ¹									
	LVN420HV / 42,000	High	1,260	70	77	83	90	96	98	104	108	116*
Mid		1,100	65	71	79	86	92	96	102	106	114	—
Low		1,000	61	67	75	82	88	94	100	104	112	116*
LVN480HV / 48,000	High	1,400	77	82	87	94	100	102	106	110	116*	—
	Mid	1,260	70	77	83	90	96	98	104	108	114	116*
	Low	1,000	61	67	75	82	88	94	100	104	112	116*
LVN600HV / 60,000	High	1,475	77	82	87	93	98	105	110	113	115	115
	Mid	1,400	74	79	84	91	96	102	110	113	115	115
	Low	1,260	67	75	80	87	90	98	102	110	115	115

¹ Unless otherwise noted, Vertical Air Handling units are UL listed up to 0.5 in. wg total static pressure, including coil, case, duct work pressure drop, air filter, and largest kW size heater. Internal static pressure includes coil and case only.

* Airflow rate (CFM) decreases by 3% per 0.1 in. wg.

Factory default status is 0.3 in wg.

Factory default is high static pressure.

Note:

- If the ESP is set incorrectly, the air conditioning may malfunction.
- To get the desired air flow and external static pressure combination, use the setting value from the table. Using a setting value other than the values listed in the table will not provide the desired combination.

EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES

Air Filter Static Pressure Drop Factors

Table 20: Air Filter Static Pressure Drop Factors.

Capacity (kBtu/h [tons])	Flow Rate (CFM)	Static Pressure Drop (in wg)
18 (1.5)	High (640)	-0.04
	Middle(580)	-0.04
	Low (480)	-0.04
24 (2.0)	High (710)	-0.04
	Middle(640)	-0.04
	Low (480)	-0.04
36 (3.0)	High (990)	-0.08
	Middle(880)	-0.08
	Low (800)	-0.08
42 (3.5)	High (1260)	-0.09
	Middle(1100)	-0.08
	Low (1000)	-0.08
48 (4.0)	High (1400)	-0.09
	Middle(1260)	-0.09
	Low (1000)	-0.08
60 (5.0)	High (1475)	-0.09
	Middle(1400)	-0.09
	Low (1260)	-0.08

If the air filter has been installed, the ESP value has to be set.
For every increase in static pressure by 0.01 in. wg, the ESP value must be increased by 1.

Minimum Airflow by Heater Capacity

Table 21: Minimum Airflow by Heater Capacity.

Capacity (kBtu/h [tons])	Heater Capacity (kW)			
	3, 5	8, 10	15	20
18 (1.5)	480	480	Not available	Not available
24 (2.0)	480	480	Not available	Not available
36 (3.0)	900	900	Not available	Not available
42 (3.5)	1000	1000	1000	1000
48 (4.0)	1000	1000	1000	1000
60 (5.0)	1260	1260	1260	1260

Airflow rates in the table above are listed in CFM.

⚠ WARNING

⊘ Do not operate with less than the minimum airflow. If an airflow is used below the minimum, there is a risk of fire, which may lead to physical injury or death.

Note:

⊘ Do not operate with less than the minimum airflow. If an airflow is used below the minimum, there is a risk of damage to the product.

Note:

If a Third-Party Dry Contact and an LG internal heater or an LG Auxiliary Heat Kit is installed, supplemental heat capability cannot be controlled by the Third-Party Thermostat.

EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES

Electric Heater Static Pressure Drop Factors

Table 22: Electric Heater Static Pressure Drop Factors.

Heater Capacity (kW)	Static Pressure Drop (in. wg)
0	0
3, 5	-0.01
8, 10	-0.02
15	-0.03
20	-0.04

in wg = inch water gauge

If the electric heater has been installed, then the ESP value has to be set.

For every increase in static pressure by 0.01 in wg, the ESP value must be increased by 1.

If the ESP setting value is inappropriate, the provided safety device will turn the heater off according to the airflow.

Down Flow (optional) Static Pressure Drop Factors

Table 23: Down Flow Static Pressure Drop Factors.

Capacity (kBtu/h [tons])	Flow Rate (CFM)	Static Pressure Drop (in wg)
18 (1.5)	High (640)	-0.04
	Middle (580)	-0.04
	Low (480)	-0.04
24 (2.0)	High (710)	-0.04
	Middle (640)	-0.04
	Low (480)	-0.04
36 (3.0)	High (990)	-0.09
	Middle (880)	-0.09
	Low (800)	-0.09
42 (3.5)	High (1260)	-0.09
	Middle (1100)	-0.09
	Low (1000)	-0.09
48 (4.0)	High (1400)	-0.09
	Middle (1260)	-0.09
	Low (1000)	-0.09
60 (5.0)	High (1475)	-0.09
	Middle(1400)	-0.09
	Low (1260)	-0.09

If the air filter has been installed, the ESP value has to be set.

For every increase in static pressure by 0.01 in. wc, the ESP value must be increased by 1.

EXTERNAL STATIC PRESSURE AND AIRFLOW RANGES

Down Flow - Air Filter (optional) Static Pressure Drop Factors

Table 24: Down Flow - Air Filter Static Pressure Drop Factors.

Capacity (kBtu/h [tons])	Flow Rate (CFM)	Static Pressure Drop (in wg)
18 (1.5)	High (640)	-0.04
	Middle(580)	-0.04
	Low (480)	-0.04
24 (2.0)	High (710)	-0.04
	Middle(640)	-0.04
	Low (480)	-0.04
36 (3.0)	High (990)	-0.06
	Middle(880)	-0.06
	Low (800)	-0.06
42 (3.5)	High (1260)	-0.07
	Middle(1100)	-0.06
	Low (1000)	-0.06
48 (4.0)	High (1400)	-0.07
	Middle(1260)	-0.07
	Low (1000)	-0.06
60 (5.0)	High (1475)	-0.07
	Middle(1400)	-0.07
	Low (1260)	-0.07

If the air filter has been installed, the ESP value has to be set.
 For every increase in static pressure by 0.01 in. wc, the ESP value must be increased by 1.

Down Flow - Internal Electric Heater Static Pressure Drop Factors

Table 25: Internal Electric Heater Static Pressure Drop Factors.

Heater Capacity (kW)	Static Pressure Drop (in. wg)
0	0
3, 5	-0.01
8, 10	-0.01
15	-0.01
20	-0.01

in. wc = inch water column, inAq
 If the internal electric heater has been installed, then the ESP value has to be set.
 For every increase in static pressure by 0.01 in WC, the ESP value must be increased by 1.
 If the ESP setting value is inappropriate, the provided safety device will turn the heater off according to the airflow.


Electric Heater

Table 26: Electric Heater Capacities for Vertical Air Handling Units.

Accessory	Model Number
3kW Electric Heater	ANEH033B1
5kW Electric Heater	ANEH053B1
8kW Electric Heater	ANEH083B2
10kW Electric Heater	ANEH103B2
15kW Electric Heater	ANEH153B2
20kW Electric Heater	ANEH203B2

Figure 54: Electric Heater.

Example: 5kW Capacity Heater



Note:

If a Third-Party Dry Contact and an LG internal heater or an LG Auxiliary Heat Kit is installed, supplemental heat capability cannot be controlled by the Third-Party Thermostat.

Table 27: Electric Heater Capacities.

Indoor Unit Model No. / Capacity (MBh)	Model Number / Heater Capacity					
	ANEH033B1 (3kW)	ANEH053B1 (5kW)	ANEH083B2 (8kW)	ANEH103B2 (10kW)	ANEH153B2 (15kW)	ANEH203B2 (20kW)
LVN181HV4 (18)	√	√	√	√	X	X
LVN241HV4 (24)	√	√	√	√	X	X
LVN361HV4 (36)	√	√	√	√	X	X
LVN420HV (42)	√	√	√	√	√	√
LVN480HV (48)	√	√	√	√	√	√
LVN600HV (60)	√	√	√	√	√	√

√ = Standard feature

X = Not Available

Note:

Image shown above may vary depending on model capacity.

ACCESSORIES

Drain Pan Heater

Figure 55: Drain Pan Heater.



Table 28: Drain Pan Heater Capacities.

System	IDU	ODU	Heater kW	Accessory Model	Note
LV181HV	LVN181HV4	LUU180HV	120 W	PQSH1200	Optional
LV241HV	LVN241HV4	LUU240HV	120 W	PQSH1200	Optional
LV300HV	LVN300HCV	LUU360HV	120 W	PQSH1200	Optional
LV361HV	LVN361HV4	LUU360HV	120 W	PQSH1200	Optional
LV420HV1	LVN420HV	LUU420HV	120 W	PQSH1200	Optional
LV420HV2	LVN420HV	LUU601HV	120 W	PQSH1200	Optional
LV480HV1	LVN480HV	LUU480HV	120 W	PQSH1200	Optional
LV480HV2	LVN480HV	LUU601HV	120 W	PQSH1200	Optional
LV600HV	LVN600HV	LUU601HV	120 W	PQSH1200	Optional


LG Monitoring View (LGMV) Diagnostic Software and Cable

LGMV software allows the service technician or commissioning agent to connect a computer USB port to the outdoor unit main printed circuit board (PCB) using an accessory cable without the need for a separate interface device. The main screen for LGMV allows user to view the following real time data on one screen:

- Actual inverter compressor speed
- Target inverter compressor speed
- Actual outdoor fan speed
- Target outdoor unit fan speed
- Actual superheat
- Target superheat
- Actual subcooler circuit superheat
- Target subcooler circuit superheat
- Main EEV position
- Subcooling EEV position
- Inverter compressor current transducer value
- Outdoor air temperature
- Actual high pressure/saturation temperature
- Actual low pressure/saturation temperature
- Suction temperature
- Inverter compressor discharge temperature
- Constant speed compressor discharge temperature
- Front outdoor coil pipe temperature
- Back outdoor coil pipe temperature
- Liquid line pipe temperature
- Subcooler inlet temperature
- Subcooler outlet temperature
- Average indoor unit (IDU) pipe temperature
- Inverter compressor operation indicator light
- Four-way reversing valve operation indicator light
- Pressure graph showing actual low pressure and actual high pressure levels
- Error code display
- Operating mode indicator
- Target high pressure
- Target low pressure
- PCB (printed circuit board) version
- Software version
- Installer name
- Model no. of outdoor units
- Site name
- Total number of connected indoor units
- Communication indicator lights
- Indoor unit capacity
- Indoor unit operating mode
- Indoor unit fan speed
- Indoor unit EEV position
- Indoor unit room temperature
- Indoor unit inlet pipe temperature
- Indoor unit outlet pipe temperature
- Indoor unit error code



Figure 56: Sample Cycleview.



Additional screens can be accessed by tabs on the main screen:

1. Cycleview: Graphic of internal components including:
 - Compressors showing actual speeds
 - EEVs
 - Indoor Units
 - Liquid injection valves
 - Temperature and pressure sensors
 - Four-way reversing valve
 - Outdoor fans showing status and speeds
2. Graph: Full screen graph of actual high and low pressures and high and low pressure limits. A sliding bar enables user to go back in time and view data.
3. Control IDU: Enables user to turn on all IDU's default setpoints of 86°F in heat mode or 64°F in cool mode.
4. Setting: Converts metric values to imperial values.
5. Making Data: Recording of real time data to a separate file created to be stored on the user's computer.
6. Loading Data: Recorded data from a saved ".CSV" file can be loaded to create an LGMV session.
7. Electrical Data: The lower half of main screen is changed to show the following:
 - Inverter compressor
 - Amps
 - Volts
 - Power Hz
 - Inverter control board fan Hz
 - Constant compressor
 - Current transducer value
 - Phase

In lieu of connecting to the outdoor unit, user has the option to connect to the indoor unit with the use of a USB to RS-485 connector kit. When connected through the indoor unit, user will not be able to record data.

This software can be used to both commission new systems and troubleshoot existing systems. LGMV data can be recorded to a ".CSV" file and emailed to an LG representative to assist with diagnostic evaluations.

Recommended Minimum PC Configuration:

- CPU: Pentium® IV 1.6 GHz
- Operating System: Windows® NT/2000/XP/Vista
- Main Memory: 256 MB
- Hard Disk: 600 MB when operating
- Web Browser: Internet Explorer® 5.0

LGMV is available in different formats, including Mobile LGMV, which is a app for use on wireless devices. Contact your LG Sales Representative for more information.

ACCESSORIES

LG Smart ThinQ


LG Smart ThinQ is an optional Wi-Fi module, along with a free smart phone app that provides monitoring and remote control capabilities for certain LG single zone systems. The app has the following features and benefits:

- Sign in to the app using LG credentials, or using Google® or Facebook® login credentials. Users only have to log in to the app once; the app remembers login details for subsequent logins.
- View current temperature settings of the air conditioning unit and change temperature, fan speed, and air flow direction from anywhere in the house or at a remote location (through the use of wireless connection). Multiple users can control the household air conditioning unit remotely.
- Monitor filter usage of the unit.
- Set up weekly schedules to start and stop air conditioner activity.
- Set up the unit to run in different Modes, depending on the user's schedule. Set up specific temperatures for when the user is home, away on vacation, or sleeping.
- Troubleshoot problems, and view tips on general maintenance of the system using the Smart Diagnosis function.

**Google is a registered trademark of Google Inc.; Facebook is a registered trademark of Facebook.*

Contact your LG Sales Representative or visit www.lg-dfs.com for system requirements, how to download the app, a user's manual, or other information.

Figure 57: Example of an LG Smart ThinQ Screen (appearances may differ depending on version of software).



VERTICAL AIR HANDLING UNIT PERFORMANCE DATA

[Cooling Capacity Data on page 62](#)

[Heating Capacity Data on page 71](#)

[Maximum Heating Capacity Data on page 80](#)

[Equipment Selection Procedure on page 89](#)

PERFORMANCE DATA

Cooling Capacity Tables

Cooling Capacity Table for LV181HV (LUU180HV + LVN181HV4)

Table 29: Cooling Capacity Table for LUU180HV + LVN181HV4.

Outdoor Air Temp. (°F DB)	Indoor Air Temperature: °F DB / °F WB																	
	68 / 57			72 / 61			77 / 64			80 / 67			86 / 72			90 / 75		
	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI
-4	17.70	13.35	0.86	18.80	14.10	0.90	19.89	13.66	0.93	20.69	13.94	0.94	22.09	14.06	0.96	23.19	14.33	0.98
-0.4	17.69	13.43	0.87	18.79	14.19	0.91	19.88	13.74	0.94	20.68	14.03	0.95	22.08	14.14	0.97	23.18	14.41	0.99
5	17.67	13.55	0.89	18.77	14.31	0.92	19.87	13.86	0.95	20.66	14.15	0.96	22.06	14.27	0.98	23.16	14.54	1.00
10	17.66	13.65	0.90	18.76	14.42	0.93	19.85	13.97	0.97	20.64	14.26	0.98	22.05	14.38	1.00	23.14	14.65	1.02
15	17.65	13.76	0.91	18.74	14.54	0.95	19.84	14.08	0.98	20.63	14.37	0.99	22.03	14.49	1.01	23.12	14.77	1.03
20	17.63	13.87	0.93	18.73	14.65	0.96	19.82	14.19	1.00	20.61	14.49	1.01	22.01	14.61	1.03	23.11	14.88	1.05
25	17.62	13.98	0.94	18.71	14.77	0.97	19.81	14.30	1.01	20.60	14.60	1.02	22.00	14.72	1.04	23.09	15.00	1.06
30	17.60	14.08	0.95	18.70	14.88	0.99	19.79	14.41	1.02	20.58	14.71	1.04	21.98	14.83	1.06	23.07	15.11	1.08
35	17.59	14.19	0.97	18.68	14.99	1.00	19.78	14.52	1.04	20.57	14.82	1.05	21.96	14.95	1.07	23.05	15.23	1.09
40	17.58	14.30	0.98	18.67	15.10	1.02	19.76	14.63	1.05	20.55	14.93	1.06	21.94	15.06	1.08	23.04	15.34	1.11
45	17.56	14.41	0.99	18.66	15.22	1.03	19.75	14.73	1.07	20.53	15.04	1.08	21.93	15.17	1.10	23.02	15.46	1.12
50	17.55	14.51	1.01	18.64	15.33	1.04	19.73	14.84	1.08	20.52	15.16	1.09	21.91	15.28	1.11	23.00	15.57	1.14
55	17.54	14.62	1.02	18.63	15.44	1.06	19.72	14.95	1.09	20.50	15.27	1.11	21.89	15.40	1.13	22.98	15.69	1.15
60	17.52	14.72	1.03	18.61	15.55	1.07	19.70	15.06	1.11	20.49	15.38	1.12	21.88	15.51	1.14	22.97	15.80	1.17
65	17.51	14.83	1.04	18.60	15.67	1.08	19.69	15.17	1.12	20.47	15.49	1.14	21.86	15.62	1.16	22.95	15.91	1.18
70	17.50	14.94	1.06	18.58	15.78	1.10	19.67	15.28	1.14	20.46	15.60	1.15	21.84	15.73	1.17	22.93	16.03	1.19
75	17.08	14.69	1.12	18.16	15.54	1.16	19.24	15.06	1.20	20.03	15.39	1.21	21.41	15.54	1.23	22.50	15.85	1.26
80	16.66	14.44	1.17	17.74	15.29	1.22	18.82	14.84	1.26	19.60	15.18	1.27	20.98	15.34	1.30	22.06	15.66	1.32
85	16.24	14.18	1.23	17.32	15.04	1.27	18.40	14.61	1.32	19.17	14.95	1.34	20.55	15.14	1.36	21.63	15.46	1.39
90	15.82	13.91	1.29	16.90	14.77	1.33	17.97	14.37	1.38	18.75	14.72	1.40	20.12	14.92	1.42	21.20	15.26	1.45
95	15.37	13.76	1.34	16.44	14.64	1.39	17.51	14.27	1.44	18.00	14.40	1.46	19.65	14.84	1.49	20.72	15.19	1.52
100	14.99	13.39	1.40	16.06	14.27	1.45	17.13	13.92	1.50	17.77	14.18	1.52	19.28	14.52	1.55	20.35	14.88	1.58
105	14.62	13.02	1.46	15.69	13.90	1.51	16.76	13.59	1.57	17.53	13.95	1.58	18.90	14.21	1.61	19.97	14.57	1.65
110	14.24	12.58	1.51	15.32	13.45	1.57	16.39	13.17	1.63	17.16	13.54	1.65	18.53	13.80	1.68	19.60	14.17	1.71
115	13.87	12.20	1.57	14.94	13.07	1.63	16.01	12.82	1.69	16.79	13.19	1.71	18.15	13.47	1.74	19.22	13.85	1.78
118	13.65	12.11	1.61	14.72	12.99	1.66	15.79	12.75	1.73	16.56	13.13	1.75	17.93	13.43	1.78	19.00	13.81	1.81
122	13.57	12.08	1.65	14.64	12.97	1.71	15.71	12.73	1.77	16.49	13.11	1.79	17.85	13.41	1.83	18.92	13.80	1.87

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)
 SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)
 1. All capacities are net, evaporator fan motor heat is deducted.
 2. Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
 3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible. ⚠ Do not extrapolate.
 Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.
 0 ft. level difference between outdoor and indoor units.
 Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

PERFORMANCE DATA

Cooling Capacity Tables

Cooling Capacity Table for LV241HV (LUU240HV + LVN241HV4)

Table 30: Cooling Capacity Table for LUU240HV + LVN241HV4.

Outdoor Air Temp. (°F DB)	Indoor Air Temperature: °F DB / °F WB																	
	68 / 57			72 / 61			77 / 64			80 / 67			86 / 72			90 / 75		
	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI
-4	22.81	17.17	1.17	24.22	18.13	1.22	25.65	17.55	1.25	26.66	17.92	1.27	28.48	18.08	1.30	29.89	18.42	1.32
-0.4	22.79	17.26	1.19	24.22	18.24	1.23	25.63	17.66	1.27	26.65	18.03	1.28	28.46	18.18	1.31	29.88	18.53	1.34
5	22.77	17.42	1.21	24.20	18.40	1.24	25.61	17.82	1.29	26.63	18.18	1.31	28.44	18.34	1.33	29.85	18.69	1.36
10	22.77	17.55	1.23	24.18	18.54	1.26	25.59	17.95	1.31	26.61	18.33	1.33	28.41	18.48	1.35	29.83	18.84	1.38
15	22.75	17.69	1.24	24.16	18.69	1.28	25.57	18.10	1.33	26.58	18.47	1.35	28.39	18.64	1.37	29.80	18.99	1.40
20	22.73	17.84	1.25	24.14	18.84	1.30	25.55	18.24	1.35	26.56	18.62	1.37	28.37	18.78	1.40	29.78	19.13	1.42
25	22.71	17.97	1.27	24.12	18.99	1.32	25.53	18.38	1.37	26.54	18.76	1.39	28.35	18.93	1.41	29.76	19.29	1.44
30	22.69	18.11	1.29	24.10	19.13	1.34	25.51	18.52	1.39	26.53	18.91	1.40	28.32	19.07	1.43	29.73	19.43	1.46
35	22.68	18.24	1.31	24.08	19.28	1.36	25.49	18.66	1.40	26.51	19.05	1.42	28.30	19.22	1.45	29.72	19.58	1.48
40	22.66	18.39	1.33	24.06	19.42	1.38	25.47	18.80	1.42	26.49	19.20	1.44	28.28	19.36	1.47	29.70	19.73	1.50
45	22.64	18.52	1.35	24.04	19.57	1.40	25.45	18.94	1.44	26.47	19.34	1.46	28.27	19.51	1.49	29.67	19.87	1.52
50	22.62	18.66	1.37	24.02	19.71	1.41	25.43	19.08	1.46	26.45	19.49	1.48	28.24	19.65	1.51	29.65	20.02	1.54
55	22.60	18.79	1.39	24.01	19.86	1.43	25.41	19.22	1.48	26.43	19.62	1.50	28.22	19.79	1.53	29.62	20.16	1.56
60	22.59	18.93	1.40	23.99	19.99	1.45	25.39	19.36	1.50	26.41	19.77	1.52	28.20	19.93	1.55	29.60	20.31	1.58
65	22.57	19.06	1.41	23.97	20.14	1.47	25.38	19.50	1.52	26.38	19.91	1.54	28.18	20.08	1.57	29.58	20.45	1.60
70	22.55	19.20	1.43	23.95	20.28	1.49	25.36	19.64	1.55	26.36	20.05	1.56	28.16	20.22	1.58	29.55	20.61	1.62
75	22.01	18.89	1.51	23.40	19.97	1.57	24.80	19.36	1.62	25.81	19.79	1.64	27.60	19.98	1.68	28.99	20.37	1.71
80	21.47	18.56	1.59	22.86	19.66	1.65	24.25	19.08	1.71	25.26	19.52	1.73	27.04	19.73	1.76	28.44	20.14	1.79
85	20.93	18.22	1.67	22.32	19.33	1.73	23.71	18.78	1.79	24.72	19.23	1.81	26.49	19.46	1.85	27.88	19.87	1.89
90	20.39	17.88	1.74	21.78	19.00	1.81	23.16	18.48	1.88	24.17	18.93	1.90	25.94	19.19	1.93	27.33	19.62	1.97
95	19.81	17.69	1.82	21.19	18.82	1.89	22.57	18.34	1.96	23.20	18.51	1.98	25.33	19.08	2.02	26.71	19.54	2.06
100	19.32	17.22	1.90	20.71	18.35	1.97	22.09	17.90	2.04	22.90	18.22	2.06	24.84	18.68	2.10	26.23	19.13	2.15
105	18.84	16.74	1.98	20.22	17.87	2.05	21.61	17.47	2.12	22.60	17.94	2.15	24.36	18.26	2.19	25.74	18.73	2.23
110	18.36	16.17	2.06	19.74	17.29	2.13	21.12	16.93	2.21	22.12	17.40	2.23	23.88	17.75	2.27	25.26	18.22	2.32
115	17.87	15.69	2.13	19.26	16.81	2.21	20.64	16.47	2.29	21.63	16.96	2.32	23.39	17.32	2.36	24.78	17.81	2.40
118	17.58	15.57	2.18	18.97	16.70	2.25	20.35	16.39	2.34	21.34	16.89	2.37	23.10	17.26	2.41	24.49	17.76	2.46
122	17.50	15.53	2.24	18.87	16.67	2.32	20.25	16.37	2.40	21.25	16.86	2.43	23.02	17.25	2.48	24.39	17.74	2.53

Product Data

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)
 SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

- All capacities are net, evaporator fan motor heat is deducted.
- Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
- Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible. ⚠ Do not extrapolate.
 Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.
 0 ft. level difference between outdoor and indoor units.
 Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

PERFORMANCE DATA

Cooling Capacity Tables

Cooling Capacity Table for LV300HV (LUU360HV + LVN300HCV)

Table 31: Cooling Capacity Table for LUU360HV + LVN300HCV.

Outdoor Air Temp. (°F DB)	Indoor Air Temperature: °F DB / °F WB																	
	68 / 57			72 / 61			77 / 64			80 / 67			86 / 72			90 / 75		
	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI
-4	29.49	20.58	1.38	31.33	21.75	1.44	33.16	21.05	1.49	34.48	21.50	1.50	36.83	21.68	1.53	38.65	22.09	1.56
-0.4	29.48	20.71	1.40	31.31	21.87	1.45	33.14	21.18	1.50	34.46	21.62	1.52	36.80	21.81	1.55	38.63	22.22	1.58
5	29.45	20.88	1.42	31.28	22.07	1.47	33.11	21.36	1.53	34.43	21.81	1.55	36.77	22.00	1.57	38.60	22.41	1.60
10	29.43	21.05	1.45	31.26	22.23	1.50	33.08	21.53	1.55	34.41	21.98	1.57	36.74	22.17	1.60	38.57	22.59	1.63
15	29.41	21.22	1.47	31.23	22.41	1.52	33.06	21.70	1.57	34.38	22.16	1.59	36.72	22.34	1.62	38.54	22.77	1.65
20	29.38	21.39	1.49	31.21	22.59	1.54	33.03	21.87	1.60	34.36	22.33	1.62	36.68	22.52	1.65	38.51	22.95	1.67
25	29.37	21.55	1.51	31.19	22.76	1.56	33.01	22.04	1.62	34.33	22.50	1.64	36.66	22.70	1.67	38.48	23.12	1.70
30	29.34	21.71	1.52	31.17	22.94	1.58	32.98	22.21	1.64	34.30	22.68	1.66	36.63	22.87	1.69	38.45	23.30	1.72
35	29.32	21.88	1.55	31.14	23.11	1.60	32.96	22.38	1.66	34.28	22.85	1.68	36.60	23.04	1.72	38.43	23.48	1.75
40	29.30	22.04	1.57	31.12	23.28	1.62	32.93	22.54	1.69	34.25	23.02	1.70	36.58	23.22	1.74	38.39	23.66	1.77
45	29.28	22.21	1.59	31.09	23.46	1.65	32.91	22.71	1.71	34.23	23.19	1.73	36.55	23.39	1.76	38.37	23.84	1.80
50	29.25	22.38	1.61	31.07	23.63	1.67	32.88	22.88	1.73	34.20	23.37	1.75	36.52	23.56	1.78	38.33	24.01	1.82
55	29.23	22.54	1.63	31.04	23.80	1.69	32.86	23.05	1.75	34.18	23.53	1.77	36.49	23.74	1.81	38.31	24.19	1.85
60	29.21	22.70	1.65	31.03	23.98	1.72	32.83	23.22	1.77	34.14	23.71	1.80	36.47	23.90	1.83	38.28	24.36	1.87
65	29.18	22.86	1.67	31.00	24.15	1.74	32.81	23.38	1.80	34.12	23.88	1.82	36.43	24.08	1.85	38.25	24.53	1.89
70	29.16	23.02	1.70	30.98	24.32	1.76	32.78	23.55	1.82	34.09	24.05	1.85	36.41	24.25	1.87	38.22	24.71	1.92
75	28.46	22.64	1.79	30.27	23.95	1.85	32.08	23.22	1.92	33.38	23.73	1.94	35.68	23.95	1.98	37.49	24.43	2.02
80	27.76	22.26	1.88	29.56	23.58	1.95	31.37	22.88	2.02	32.67	23.40	2.04	34.97	23.65	2.08	36.77	24.15	2.13
85	27.07	21.86	1.97	28.86	23.18	2.04	30.66	22.53	2.12	31.96	23.06	2.14	34.25	23.33	2.18	36.05	23.84	2.23
90	26.37	21.44	2.06	28.16	22.78	2.14	29.95	22.16	2.22	31.25	22.70	2.24	33.54	23.01	2.28	35.33	23.53	2.33
95	25.62	21.22	2.15	27.40	22.57	2.23	29.18	21.99	2.31	30.00	22.20	2.34	32.75	22.89	2.38	34.53	23.42	2.43
100	24.99	20.65	2.25	26.78	22.00	2.33	28.56	21.47	2.41	29.61	21.86	2.44	32.13	22.39	2.48	33.91	22.94	2.53
105	24.37	20.08	2.33	26.15	21.44	2.42	27.93	20.94	2.51	29.23	21.51	2.54	31.50	21.90	2.58	33.28	22.46	2.64
110	23.74	19.40	2.43	25.53	20.74	2.52	27.31	20.30	2.60	28.60	20.87	2.64	30.88	21.28	2.69	32.67	21.85	2.74
115	23.12	18.81	2.52	24.90	20.15	2.61	26.68	19.76	2.70	27.98	20.34	2.74	30.26	20.77	2.79	32.04	21.35	2.85
118	22.74	18.68	2.58	24.53	20.04	2.67	26.31	19.66	2.76	27.60	20.25	2.80	29.88	20.70	2.85	31.67	21.29	2.91
122	22.62	18.63	2.648	24.4	19.99	2.741	26.19	19.62	2.841	27.48	20.22	2.877	29.76	20.67	2.934	31.54	21.27	2.991

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)
 SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

- All capacities are net, evaporator fan motor heat is deducted.
- Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
- Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible. ⚠ Do not extrapolate.
 Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.
 0 ft. level difference between outdoor and indoor units.
 Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

PERFORMANCE DATA

Cooling Capacity Tables

Cooling Capacity Table for LV361HV (LUU360HV + LVN361HV4)

Table 32: Cooling Capacity Table for LUU360HV + LVN361HV4.

Outdoor Air Temp. (°F DB)	Indoor Air Temperature: °F DB / °F WB																	
	68 / 57			72 / 61			77 / 64			80 / 67			86 / 72			90 / 75		
	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI
-4	32.64	22.62	1.65	34.67	23.90	1.71	36.70	23.14	1.77	38.16	23.63	1.79	40.75	23.83	1.83	42.77	24.28	1.86
-0.4	32.62	22.76	1.67	34.65	24.04	1.73	36.68	23.28	1.79	38.13	23.77	1.82	40.73	23.97	1.85	42.75	24.42	1.89
5	32.59	22.95	1.70	34.62	24.25	1.76	36.64	23.48	1.83	38.11	23.98	1.84	40.69	24.18	1.88	42.72	24.63	1.91
10	32.57	23.14	1.72	34.59	24.44	1.78	36.61	23.66	1.85	38.08	24.16	1.87	40.66	24.37	1.90	42.68	24.84	1.95
15	32.55	23.32	1.75	34.56	24.63	1.81	36.58	23.86	1.88	38.05	24.36	1.89	40.63	24.56	1.94	42.65	25.03	1.97
20	32.52	23.51	1.77	34.54	24.83	1.83	36.56	24.04	1.90	38.02	24.55	1.93	40.60	24.75	1.96	42.62	25.22	2.00
25	32.50	23.68	1.80	34.52	25.02	1.86	36.53	24.23	1.93	37.99	24.73	1.95	40.57	24.95	1.99	42.59	25.42	2.03
30	32.47	23.87	1.82	34.49	25.21	1.89	36.50	24.41	1.95	37.96	24.93	1.98	40.54	25.14	2.01	42.55	25.61	2.06
35	32.44	24.05	1.84	34.46	25.41	1.91	36.47	24.60	1.98	37.93	25.11	2.01	40.50	25.32	2.05	42.52	25.80	2.08
40	32.43	24.23	1.87	34.44	25.59	1.94	36.45	24.78	2.01	37.90	25.31	2.03	40.48	25.52	2.07	42.49	26.01	2.12
45	32.40	24.41	1.89	34.41	25.79	1.96	36.42	24.96	2.04	37.88	25.49	2.06	40.45	25.71	2.10	42.46	26.20	2.14
50	32.37	24.60	1.92	34.38	25.98	1.99	36.39	25.15	2.06	37.85	25.68	2.09	40.41	25.90	2.12	42.42	26.39	2.17
55	32.35	24.77	1.95	34.35	26.16	2.01	36.36	25.33	2.09	37.82	25.87	2.12	40.38	26.09	2.16	42.39	26.59	2.20
60	32.32	24.96	1.97	34.33	26.36	2.05	36.34	25.52	2.12	37.78	26.06	2.14	40.36	26.27	2.18	42.36	26.77	2.23
65	32.30	25.13	2.00	34.31	26.55	2.07	36.31	25.70	2.14	37.76	26.25	2.17	40.32	26.47	2.21	42.33	26.97	2.25
70	32.27	25.31	2.02	34.28	26.74	2.10	36.28	25.89	2.18	37.73	26.43	2.20	40.29	26.65	2.24	42.29	27.16	2.29
75	31.49	24.89	2.13	33.50	26.33	2.21	35.50	25.53	2.29	36.94	26.08	2.31	39.49	26.33	2.36	41.49	26.86	2.41
80	30.72	24.47	2.24	32.71	25.91	2.32	34.71	25.15	2.41	36.15	25.72	2.43	38.70	26.00	2.48	40.69	26.54	2.53
85	29.95	24.02	2.35	31.94	25.48	2.43	33.93	24.76	2.53	35.37	25.34	2.55	37.90	25.65	2.60	39.90	26.20	2.65
90	29.18	23.57	2.46	31.16	25.04	2.55	33.14	24.36	2.64	34.58	24.96	2.67	37.12	25.29	2.72	39.10	25.86	2.77
95	28.35	23.32	2.57	30.32	24.81	2.66	32.30	24.17	2.76	33.20	24.40	2.79	36.24	25.16	2.84	38.22	25.75	2.90
100	27.66	22.70	2.68	29.63	24.18	2.77	31.60	23.60	2.88	32.77	24.02	2.91	35.55	24.61	2.96	37.53	25.21	3.02
105	26.97	22.07	2.78	28.94	23.56	2.88	30.91	23.02	2.99	32.34	23.65	3.03	34.86	24.07	3.08	36.83	24.69	3.15
110	26.27	21.32	2.89	28.25	22.80	3.00	30.22	22.31	3.11	31.65	22.94	3.15	34.17	23.39	3.21	36.15	24.01	3.27
115	25.58	20.68	3.00	27.56	22.15	3.11	29.53	21.72	3.23	30.96	22.35	3.27	33.49	22.83	3.33	35.46	23.47	3.40
118	25.17	20.53	3.07	27.14	22.02	3.18	29.11	21.61	3.29	30.54	22.25	3.34	33.07	22.75	3.40	35.04	23.41	3.46
122	25.03	20.48	3.16	27.00	21.98	3.27	28.99	21.57	3.39	30.41	22.23	3.43	32.93	22.72	3.50	34.91	23.38	3.57

Product Data

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)
 SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)
 1. All capacities are net, evaporator fan motor heat is deducted.
 2. Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
 3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible. ⚠ Do not extrapolate.
 Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.
 0 ft. level difference between outdoor and indoor units.
 Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

PERFORMANCE DATA

Cooling Capacity Tables

Cooling Capacity Table for LV420HV1 (LUU420HV + LVN420HV)

Table 33: Cooling Capacity Table for LUU420HV + LVN420HV.

Outdoor Air Temp. (°F DB)	Indoor Air Temperature: °F DB / °F WB																	
	68 / 57			72 / 61			77 / 64			80 / 67			86 / 72			90 / 75		
	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI
-4	41.29	29.99	2.31	43.86	31.68	2.40	46.42	30.67	2.49	48.27	31.32	2.51	51.55	31.58	2.56	54.11	32.18	2.61
-0.4	41.27	30.16	2.34	43.83	31.86	2.42	46.40	30.85	2.51	48.25	31.50	2.54	51.52	31.77	2.59	54.08	32.37	2.64
5	41.24	30.42	2.38	43.80	32.14	2.46	46.36	31.12	2.55	48.21	31.77	2.58	51.48	32.04	2.63	54.04	32.65	2.68
10	41.20	30.67	2.41	43.76	32.39	2.50	46.32	31.37	2.59	48.17	32.03	2.62	51.44	32.30	2.67	54.00	32.91	2.72
15	41.17	30.91	2.45	43.73	32.65	2.54	46.29	31.61	2.63	48.13	32.28	2.66	51.40	32.55	2.71	53.96	33.17	2.76
20	41.14	31.15	2.48	43.70	32.91	2.57	46.25	31.86	2.67	48.10	32.53	2.70	51.36	32.81	2.75	53.92	33.43	2.80
25	41.11	31.39	2.52	43.66	33.16	2.61	46.22	32.11	2.70	48.06	32.78	2.74	51.32	33.06	2.79	53.88	33.69	2.84
30	41.08	31.63	2.55	43.63	33.41	2.65	46.18	32.35	2.74	48.02	33.04	2.77	51.28	33.31	2.83	53.83	33.95	2.88
35	41.05	31.87	2.59	43.60	33.67	2.68	46.15	32.60	2.78	47.99	33.29	2.81	51.24	33.57	2.86	53.79	34.20	2.92
40	41.02	32.11	2.62	43.56	33.92	2.72	46.11	32.85	2.82	47.95	33.54	2.85	51.20	33.82	2.90	53.75	34.46	2.96
45	40.98	32.35	2.66	43.53	34.18	2.75	46.07	33.09	2.86	47.91	33.79	2.89	51.17	34.07	2.94	53.71	34.72	3.00
50	40.95	32.59	2.69	43.50	34.43	2.79	46.04	33.34	2.89	47.88	34.04	2.93	51.13	34.32	2.98	53.67	34.97	3.04
55	40.92	32.83	2.73	43.46	34.68	2.83	46.00	33.58	2.93	47.84	34.29	2.96	51.09	34.58	3.02	53.63	35.23	3.08
60	40.89	33.07	2.76	43.43	34.93	2.86	45.97	33.82	2.97	47.80	34.54	3.00	51.05	34.83	3.06	53.59	35.49	3.12
65	40.86	33.31	2.80	43.40	35.18	2.90	45.93	34.07	3.01	47.77	34.78	3.04	51.01	35.08	3.10	53.55	35.74	3.16
70	40.83	33.54	2.83	43.36	35.43	2.94	45.90	34.31	3.04	47.73	35.03	3.08	50.97	35.33	3.14	53.50	36.00	3.20
75	39.84	32.99	2.99	42.37	34.90	3.10	44.90	33.83	3.21	46.73	34.57	3.25	49.96	34.90	3.31	52.49	35.59	3.37
80	38.86	32.43	3.14	41.39	34.35	3.25	43.91	33.33	3.37	45.73	34.09	3.41	48.95	34.46	3.48	51.48	35.17	3.55
85	37.89	31.84	3.29	40.41	33.77	3.41	42.92	32.81	3.54	44.74	33.58	3.58	47.96	33.99	3.64	50.47	34.73	3.72
90	36.91	31.23	3.45	39.43	33.18	3.57	41.94	32.28	3.70	43.75	33.07	3.74	46.96	33.52	3.81	49.47	34.27	3.89
95	35.86	30.91	3.60	38.36	32.88	3.73	40.85	32.04	3.87	42.00	32.34	3.91	45.85	33.34	3.98	48.35	34.12	4.06
100	34.98	30.08	3.75	37.48	32.05	3.89	39.98	31.27	4.03	41.46	31.84	4.08	44.98	32.62	4.15	47.47	33.42	4.24
105	34.11	29.25	3.90	36.61	31.22	4.05	39.11	30.51	4.19	40.91	31.34	4.24	44.10	31.90	4.32	46.60	32.72	4.41
110	33.24	28.25	4.06	35.74	30.21	4.20	38.23	29.57	4.36	40.04	30.40	4.41	43.23	31.00	4.49	45.73	31.83	4.58
115	32.37	27.41	4.21	34.86	29.36	4.36	37.36	28.78	4.52	39.17	29.63	4.57	42.36	30.26	4.66	44.86	31.10	4.75
118	31.84	27.21	4.30	34.34	29.18	4.46	36.84	28.64	4.62	38.64	29.50	4.67	41.83	30.16	4.76	44.33	31.02	4.86
122	31.67	27.14	4.42	34.16	29.12	4.58	36.66	28.59	4.75	38.47	29.45	4.81	41.66	30.12	4.90	44.16	30.99	5.00

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)
 SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)
 1. All capacities are net, evaporator fan motor heat is deducted.
 2. Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
 3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible.  Do not extrapolate.
 Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping, 0 ft. level difference between outdoor and indoor units.
 Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

PERFORMANCE DATA

Cooling Capacity Tables

Cooling Capacity Table for LV420HV2 (LUU601HV + LVN420HV)

Table 34: Cooling Capacity Table for LUU601HV + LVN420HV.

Outdoor Air Temp. (°F DB)	Indoor Air Temperature: °F DB / °F WB																	
	68 / 57			72 / 61			77 / 64			80 / 67			86 / 72			90 / 75		
	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI
-4	41.29	28.82	2.12	43.86	30.44	2.20	46.42	29.48	2.28	48.27	30.10	2.31	51.55	30.35	2.35	54.11	30.93	2.40
-0.4	41.27	28.98	2.15	43.83	30.62	2.23	46.39	29.65	2.31	48.25	30.27	2.34	51.52	30.53	2.38	54.08	31.11	2.42
5	41.24	29.24	2.18	43.79	30.88	2.26	46.36	29.90	2.34	48.20	30.53	2.37	51.48	30.79	2.41	54.04	31.38	2.47
10	41.20	29.47	2.21	43.76	31.13	2.29	46.32	30.14	2.38	48.17	30.78	2.41	51.44	31.04	2.45	54.00	31.63	2.50
15	41.17	29.71	2.25	43.73	31.38	2.33	46.29	30.38	2.41	48.13	31.02	2.44	51.40	31.28	2.49	53.96	31.87	2.54
20	41.14	29.94	2.28	43.70	31.63	2.36	46.25	30.62	2.45	48.10	31.27	2.47	51.36	31.53	2.52	53.92	32.13	2.57
25	41.11	30.17	2.31	43.66	31.87	2.39	46.22	30.86	2.48	48.06	31.51	2.51	51.32	31.77	2.56	53.87	32.38	2.61
30	41.08	30.40	2.34	43.63	32.11	2.43	46.18	31.10	2.52	48.02	31.74	2.55	51.28	32.02	2.60	53.83	32.62	2.65
35	41.05	30.63	2.38	43.59	32.36	2.47	46.15	31.33	2.55	47.99	31.99	2.58	51.24	32.26	2.63	53.80	32.87	2.68
40	41.01	30.86	2.41	43.57	32.60	2.49	46.11	31.57	2.59	47.95	32.23	2.62	51.21	32.50	2.67	53.75	33.12	2.72
45	40.99	31.09	2.44	43.53	32.84	2.53	46.08	31.80	2.62	47.92	32.47	2.65	51.16	32.74	2.70	53.71	33.36	2.76
50	40.95	31.32	2.47	43.50	33.09	2.56	46.04	32.03	2.65	47.88	32.71	2.68	51.13	32.99	2.73	53.67	33.61	2.79
55	40.92	31.55	2.50	43.46	33.33	2.60	46.01	32.27	2.69	47.84	32.95	2.72	51.08	33.23	2.77	53.63	33.86	2.83
60	40.89	31.78	2.54	43.43	33.57	2.63	45.97	32.50	2.73	47.80	33.19	2.76	51.05	33.47	2.81	53.59	34.10	2.86
65	40.86	32.01	2.57	43.40	33.81	2.66	45.94	32.74	2.76	47.77	33.43	2.79	51.01	33.71	2.84	53.55	34.35	2.90
70	40.83	32.24	2.60	43.37	34.05	2.70	45.90	32.97	2.79	47.73	33.67	2.83	50.97	33.95	2.88	53.51	34.59	2.94
75	39.85	31.71	2.74	42.38	33.53	2.84	44.91	32.51	2.94	46.73	33.22	2.98	49.96	33.54	3.04	52.49	34.21	3.10
80	38.86	31.17	2.88	41.39	33.01	2.99	43.91	32.03	3.10	45.73	32.76	3.13	48.96	33.12	3.19	51.48	33.81	3.26
85	37.89	30.59	3.02	40.41	32.45	3.13	42.92	31.53	3.25	44.74	32.27	3.29	47.96	32.67	3.34	50.47	33.37	3.42
90	36.92	30.02	3.16	39.43	31.89	3.28	41.94	31.03	3.40	43.75	31.78	3.44	46.95	32.21	3.50	49.46	32.94	3.58
95	35.86	29.70	3.30	38.36	31.60	3.42	40.85	30.79	3.55	42.00	31.08	3.59	45.85	32.04	3.66	48.34	32.79	3.73
100	34.98	28.91	3.44	37.49	30.80	3.57	39.98	30.06	3.70	41.46	30.59	3.74	44.98	31.35	3.81	47.48	32.12	3.89
105	34.11	28.12	3.58	36.61	30.01	3.71	39.10	29.32	3.85	40.92	30.12	3.89	44.10	30.66	3.97	46.60	31.45	4.05
110	33.24	27.15	3.73	35.74	29.04	3.86	38.24	28.41	4.00	40.04	29.21	4.05	43.23	29.79	4.13	45.73	30.59	4.21
115	32.37	26.33	3.87	34.86	28.22	4.00	37.36	27.66	4.16	39.17	28.47	4.20	42.36	29.08	4.28	44.85	29.89	4.37
118	31.84	26.15	3.95	34.34	28.05	4.09	36.84	27.52	4.24	38.64	28.35	4.29	41.83	28.98	4.37	44.33	29.81	4.46
122	31.67	26.08	4.06	34.17	27.99	4.21	36.66	27.48	4.37	38.47	28.30	4.42	41.66	28.95	4.50	44.15	29.79	4.58

Product Data

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

- All capacities are net, evaporator fan motor heat is deducted.
- Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
- Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible.  Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

PERFORMANCE DATA

Cooling Capacity Tables

Cooling Capacity Table for LV480HV1 (LUU480HV + LVN480HV)

Table 35: Cooling Capacity Table for LUU480HV + LVN480HV.

Outdoor Air Temp. (°F DB)	Indoor Air Temperature: °F DB / °F WB																	
	68 / 57			72 / 61			77 / 64			80 / 67			86 / 72			90 / 75		
	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI
-4	47.19	33.83	2.93	50.12	35.73	3.04	53.05	34.60	3.15	55.17	35.33	3.18	58.91	35.62	3.24	61.84	36.30	3.31
-0.4	47.16	34.02	2.96	50.09	35.94	3.07	53.02	34.80	3.18	55.14	35.53	3.22	58.88	35.83	3.28	61.81	36.51	3.34
5	47.13	34.32	3.01	50.05	36.25	3.12	52.98	35.10	3.23	55.09	35.84	3.27	58.83	36.14	3.33	61.76	36.83	3.40
10	47.09	34.59	3.05	50.01	36.54	3.16	52.94	35.38	3.28	55.05	36.13	3.32	58.79	36.43	3.38	61.71	37.12	3.45
15	47.05	34.87	3.10	49.98	36.83	3.21	52.90	35.66	3.33	55.01	36.41	3.37	58.74	36.72	3.43	61.67	37.41	3.50
20	47.02	35.14	3.14	49.94	37.12	3.26	52.86	35.94	3.38	54.97	36.70	3.41	58.70	37.01	3.48	61.62	37.71	3.55
25	46.98	35.41	3.19	49.90	37.41	3.30	52.82	36.22	3.42	54.93	36.98	3.46	58.65	37.29	3.53	61.57	38.00	3.60
30	46.95	35.68	3.23	49.86	37.69	3.35	52.78	36.50	3.47	54.88	37.26	3.51	58.61	37.58	3.58	61.52	38.29	3.65
35	46.91	35.95	3.28	49.82	37.98	3.40	52.74	36.77	3.52	54.84	37.55	3.56	58.56	37.86	3.63	61.48	38.58	3.70
40	46.87	36.22	3.32	49.79	38.26	3.44	52.70	37.05	3.57	54.80	37.83	3.61	58.52	38.15	3.68	61.43	38.87	3.75
45	46.84	36.49	3.36	49.75	38.55	3.49	52.66	37.33	3.61	54.76	38.11	3.66	58.47	38.43	3.73	61.38	39.16	3.80
50	46.80	36.76	3.41	49.71	38.84	3.53	52.62	37.60	3.66	54.72	38.39	3.70	58.43	38.72	3.77	61.34	39.45	3.85
55	46.77	37.03	3.45	49.67	39.12	3.58	52.58	37.88	3.71	54.67	38.68	3.75	58.38	39.00	3.82	61.29	39.74	3.90
60	46.73	37.30	3.50	49.63	39.40	3.63	52.54	38.15	3.76	54.63	38.96	3.80	58.34	39.29	3.87	61.24	40.03	3.95
65	46.70	37.57	3.54	49.60	39.69	3.67	52.50	38.43	3.81	54.59	39.24	3.85	58.30	39.57	3.92	61.20	40.32	4.00
70	46.66	37.84	3.59	49.56	39.97	3.72	52.46	38.70	3.85	54.55	39.52	3.90	58.25	39.85	3.97	61.15	40.60	4.05
75	45.54	37.22	3.78	48.43	39.36	3.92	51.32	38.16	4.06	53.41	38.99	4.11	57.10	39.37	4.19	59.99	40.15	4.27
80	44.41	36.58	3.97	47.30	38.74	4.12	50.18	37.60	4.27	52.26	38.45	4.32	55.95	38.87	4.40	58.83	39.68	4.49
85	43.30	35.91	4.17	46.18	38.09	4.32	49.05	37.01	4.48	51.13	37.88	4.53	54.81	38.35	4.61	57.68	39.17	4.71
90	42.19	35.23	4.36	45.06	37.43	4.52	47.93	36.42	4.69	50.00	37.30	4.74	53.66	37.81	4.83	56.53	38.66	4.93
95	40.98	34.86	4.55	43.84	37.09	4.72	46.69	36.14	4.89	48.00	36.48	4.95	52.40	37.61	5.04	55.25	38.49	5.14
100	39.98	33.93	4.75	42.84	36.15	4.92	45.69	35.28	5.10	47.38	35.91	5.16	51.40	36.80	5.26	54.26	37.70	5.36
105	38.98	33.00	4.94	41.84	35.22	5.12	44.69	34.42	5.31	46.76	35.35	5.37	50.40	35.99	5.47	53.26	36.91	5.58
110	37.99	31.87	5.14	40.84	34.08	5.32	43.70	33.35	5.52	45.76	34.29	5.58	49.41	34.97	5.69	52.26	35.90	5.80
115	36.99	30.91	5.33	39.84	33.12	5.52	42.70	32.47	5.73	44.76	33.42	5.79	48.41	34.13	5.90	51.26	35.08	6.02
118	36.39	30.69	5.45	39.24	32.92	5.64	42.10	32.30	5.85	44.16	33.27	5.92	47.81	34.02	6.03	50.66	34.99	6.15
122	36.19	30.61	5.60	39.05	32.85	5.80	41.90	32.25	6.02	43.96	33.22	6.09	47.61	33.98	6.20	50.46	34.96	6.32

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.

3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible.  Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

PERFORMANCE DATA

Cooling Capacity Tables

Cooling Capacity Table for LV480HV2 (LUU601HV + LVN480HV)

Table 36: Cooling Capacity Table for LUU601HV + LVN480HV.

Outdoor Air Temp. (°F DB)	Indoor Air Temperature: °F DB / °F WB																	
	68 / 57			72 / 61			77 / 64			80 / 67			86 / 72			90 / 75		
	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI
-4	45.22	31.57	2.33	48.03	33.34	2.41	50.84	32.29	2.50	52.87	32.97	2.53	56.46	33.24	2.57	59.26	33.87	2.63
-0.4	45.20	31.74	2.35	48.00	33.54	2.44	50.81	32.47	2.53	52.84	33.15	2.56	56.43	33.43	2.61	59.23	34.07	2.65
5	45.17	32.02	2.39	47.96	33.83	2.48	50.77	32.75	2.57	52.79	33.44	2.60	56.38	33.72	2.64	59.19	34.37	2.70
10	45.13	32.28	2.42	47.93	34.10	2.51	50.73	33.01	2.61	52.76	33.71	2.64	56.34	33.99	2.68	59.14	34.64	2.74
15	45.09	32.54	2.46	47.90	34.37	2.55	50.70	33.27	2.64	52.72	33.97	2.68	56.29	34.26	2.72	59.10	34.91	2.78
20	45.06	32.79	2.49	47.86	34.64	2.59	50.66	33.54	2.68	52.68	34.25	2.71	56.25	34.53	2.76	59.05	35.19	2.82
25	45.02	33.04	2.53	47.82	34.91	2.62	50.62	33.80	2.72	52.64	34.51	2.75	56.21	34.80	2.80	59.00	35.46	2.86
30	44.99	33.29	2.57	47.78	35.17	2.66	50.58	34.06	2.76	52.59	34.77	2.79	56.17	35.07	2.84	58.96	35.73	2.90
35	44.96	33.55	2.61	47.74	35.44	2.70	50.54	34.31	2.80	52.56	35.04	2.83	56.12	35.33	2.88	58.92	36.00	2.94
40	44.92	33.80	2.64	47.72	35.70	2.73	50.50	34.57	2.84	52.52	35.30	2.87	56.08	35.60	2.92	58.87	36.27	2.98
45	44.89	34.05	2.67	47.68	35.97	2.77	50.47	34.83	2.87	52.48	35.56	2.91	56.03	35.86	2.96	58.82	36.54	3.02
50	44.85	34.30	2.71	47.64	36.24	2.80	50.43	35.09	2.91	52.44	35.82	2.94	56.00	36.13	2.99	58.78	36.81	3.06
55	44.82	34.55	2.74	47.60	36.50	2.84	50.39	35.35	2.95	52.39	36.09	2.98	55.95	36.39	3.03	58.74	37.08	3.10
60	44.78	34.81	2.78	47.56	36.76	2.88	50.35	35.60	2.99	52.35	36.35	3.02	55.91	36.66	3.07	58.69	37.35	3.14
65	44.75	35.06	2.81	47.53	37.04	2.91	50.31	35.86	3.03	52.32	36.62	3.06	55.87	36.92	3.11	58.65	37.62	3.18
70	44.72	35.31	2.85	47.50	37.30	2.95	50.27	36.11	3.06	52.28	36.88	3.10	55.82	37.18	3.15	58.60	37.88	3.22
75	43.64	34.73	3.00	46.41	36.73	3.11	49.18	35.61	3.22	51.18	36.38	3.26	54.72	36.74	3.33	57.49	37.46	3.39
80	42.56	34.13	3.15	45.33	36.15	3.27	48.09	35.09	3.39	50.08	35.88	3.43	53.62	36.27	3.49	56.38	37.03	3.57
85	41.50	33.51	3.31	44.26	35.54	3.43	47.01	34.53	3.56	49.00	35.35	3.60	52.53	35.78	3.66	55.28	36.55	3.74
90	40.43	32.87	3.46	43.18	34.93	3.59	45.93	33.98	3.73	47.92	34.81	3.76	51.42	35.28	3.84	54.17	36.07	3.92
95	39.27	32.53	3.61	42.01	34.61	3.75	44.74	33.72	3.88	46.00	34.04	3.93	50.22	35.09	4.00	52.95	35.92	4.08
100	38.31	31.66	3.77	41.06	33.73	3.91	43.79	32.92	4.05	45.41	33.51	4.10	49.26	34.34	4.18	52.00	35.18	4.26
105	37.36	30.79	3.92	40.10	32.86	4.07	42.83	32.12	4.22	44.81	32.99	4.27	48.30	33.58	4.34	51.04	34.44	4.43
110	36.41	29.74	4.08	39.14	31.80	4.23	41.88	31.12	4.38	43.85	32.00	4.43	47.35	32.63	4.52	50.08	33.50	4.61
115	35.45	28.84	4.23	38.18	30.90	4.38	40.92	30.30	4.55	42.90	31.18	4.60	46.39	31.85	4.69	49.12	32.73	4.78
118	34.87	28.64	4.33	37.61	30.72	4.48	40.35	30.14	4.65	42.32	31.04	4.70	45.82	31.74	4.79	48.55	32.65	4.88
122	34.68	28.56	4.45	37.42	30.65	4.61	40.15	30.09	4.78	42.13	31.00	4.84	45.63	31.71	4.92	48.36	32.62	5.02

Product Data

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)
 SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

- All capacities are net, evaporator fan motor heat is deducted.
- Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
- Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible.  Do not extrapolate.
 Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.
 0 ft. level difference between outdoor and indoor units.
 Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

PERFORMANCE DATA

Cooling Capacity Tables

Cooling Capacity Table for LV600HV (LUU601HV + LVN600HV)

Table 37: Cooling Capacity Table for LUU601HV + LVN600HV.

Outdoor Air Temp. (°F DB)	Indoor Air Temperature: °F DB / °F WB																	
	68 / 57			72 / 61			77 / 64			80 / 67			86 / 72			90 / 75		
	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI	TC	SHC	PI
-4	51.61	36.03	2.66	54.82	38.05	2.76	58.02	36.85	2.86	60.34	37.63	2.88	64.43	37.93	2.94	67.64	38.66	3.00
-0.4	51.58	36.23	2.68	54.79	38.27	2.78	57.99	37.06	2.88	60.31	37.84	2.92	64.40	38.16	2.97	67.60	38.88	3.03
5	51.55	36.55	2.73	54.74	38.61	2.83	57.95	37.38	2.93	60.25	38.17	2.96	64.35	38.49	3.02	67.55	39.22	3.08
10	51.50	36.84	2.76	54.70	38.91	2.86	57.90	37.68	2.97	60.21	38.48	3.01	64.30	38.80	3.06	67.50	39.53	3.13
15	51.46	37.14	2.81	54.67	39.22	2.91	57.86	37.98	3.02	60.17	38.78	3.05	64.25	39.11	3.11	67.45	39.84	3.17
20	51.43	37.42	2.85	54.62	39.53	2.96	57.82	38.27	3.06	60.12	39.08	3.09	64.20	39.41	3.15	67.40	40.16	3.22
25	51.38	37.71	2.89	54.58	39.84	2.99	57.77	38.57	3.10	60.08	39.38	3.14	64.15	39.71	3.20	67.34	40.47	3.26
30	51.35	38.00	2.93	54.53	40.14	3.04	57.73	38.87	3.15	60.03	39.68	3.18	64.10	40.02	3.25	67.29	40.78	3.31
35	51.31	38.29	2.97	54.49	40.45	3.08	57.68	39.16	3.19	59.98	39.99	3.23	64.05	40.32	3.29	67.24	41.09	3.35
40	51.26	38.57	3.01	54.46	40.75	3.12	57.64	39.46	3.24	59.94	40.29	3.27	64.01	40.63	3.34	67.19	41.40	3.40
45	51.23	38.86	3.05	54.41	41.05	3.16	57.60	39.76	3.27	59.89	40.59	3.32	63.95	40.93	3.38	67.13	41.70	3.44
50	51.19	39.15	3.09	54.37	41.36	3.20	57.55	40.04	3.32	59.85	40.88	3.35	63.91	41.24	3.42	67.09	42.01	3.49
55	51.15	39.44	3.13	54.33	41.66	3.25	57.51	40.34	3.36	59.80	41.19	3.40	63.85	41.53	3.46	67.04	42.32	3.54
60	51.11	39.72	3.17	54.28	41.96	3.29	57.47	40.63	3.41	59.75	41.49	3.44	63.81	41.84	3.51	66.98	42.63	3.58
65	51.08	40.01	3.21	54.25	42.27	3.33	57.42	40.93	3.45	59.71	41.79	3.49	63.77	42.14	3.55	66.94	42.94	3.63
70	51.03	40.30	3.25	54.21	42.57	3.37	57.38	41.21	3.49	59.66	42.09	3.54	63.71	42.44	3.60	66.88	43.24	3.67
75	49.81	39.64	3.43	52.97	41.92	3.55	56.13	40.64	3.68	58.42	41.52	3.73	62.45	41.93	3.80	65.61	42.76	3.87
80	48.57	38.96	3.60	51.73	41.26	3.73	54.88	40.04	3.87	57.16	40.95	3.92	61.20	41.40	3.99	64.35	42.26	4.07
85	47.36	38.24	3.78	50.51	40.56	3.92	53.65	39.41	4.06	55.92	40.34	4.11	59.95	40.84	4.18	63.09	41.71	4.27
90	46.15	37.52	3.95	49.28	39.86	4.10	52.42	38.79	4.25	54.69	39.72	4.30	58.69	40.27	4.38	61.83	41.17	4.47
95	44.82	37.12	4.12	47.95	39.50	4.28	51.07	38.49	4.43	52.50	38.85	4.49	57.31	40.05	4.57	60.43	40.99	4.66
100	43.73	36.13	4.31	46.86	38.50	4.46	49.97	37.57	4.62	51.82	38.24	4.68	56.22	39.19	4.77	59.35	40.15	4.86
105	42.63	35.14	4.48	45.76	37.51	4.64	48.88	36.66	4.81	51.14	37.65	4.87	55.13	38.33	4.96	58.25	39.31	5.06
110	41.55	33.94	4.66	44.67	36.29	4.82	47.80	35.52	5.00	50.05	36.52	5.06	54.04	37.24	5.16	57.16	38.23	5.26
115	40.46	32.92	4.83	43.58	35.27	5.00	46.70	34.58	5.19	48.96	35.59	5.25	52.95	36.35	5.35	56.07	37.36	5.46
118	39.80	32.68	4.94	42.92	35.06	5.11	46.05	34.40	5.30	48.30	35.43	5.37	52.29	36.23	5.47	55.41	37.26	5.57
122	39.58	32.60	5.08	42.71	34.98	5.26	45.83	34.35	5.46	48.08	35.38	5.52	52.07	36.19	5.62	55.19	37.23	5.73

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)
 SHC: Sensible Capacity (kBtu/h) PI: Power Input (kW) (includes compressor, indoor fan motor and outdoor fan motor)

- All capacities are net, evaporator fan motor heat is deducted.
- Cooling operating range with the Low Ambient Baffle Kit (sold separately) is -4°F to +122°F.
- Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

4. Direct interpolation is permissible.  Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.
 0 ft. level difference between outdoor and indoor units.

Nominal cooling capacity rating obtained with air entering the indoor unit at 80°F dry bulb (DB) and 67°F wet bulb (WB), and outdoor ambient conditions of 95°F dry bulb (DB) and 75°F wet bulb (WB).

PERFORMANCE DATA

Heating Capacity Tables

Heating Capacity Table for LV181HV (LUU180HV + LVN181HV4)

Table 38: Heating Capacity Table for LUU180HV + LVN181HV4.

Outdoor Air Temp.		Indoor Air Temp. °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	9.73	1.13	9.14	1.17	9.01	1.20	8.88	1.22	8.78	1.24	8.41	1.27
0	-0.4	10.79	1.17	10.22	1.21	10.02	1.24	9.87	1.27	9.75	1.28	9.34	1.32
5	4.5	11.96	1.22	11.42	1.26	11.14	1.30	10.96	1.32	10.81	1.33	10.38	1.37
10	9	12.96	1.26	12.44	1.30	12.09	1.34	11.89	1.37	11.72	1.38	11.26	1.42
17	15	14.16	1.32	13.67	1.36	13.24	1.41	13.00	1.43	12.81	1.45	12.32	1.49
20	19	14.92	1.36	14.45	1.40	13.97	1.45	13.71	1.47	13.50	1.49	12.99	1.54
25	23	16.20	1.40	15.72	1.45	15.17	1.49	14.89	1.52	14.66	1.54	14.11	1.58
30	28	17.49	1.45	16.95	1.50	16.37	1.54	16.07	1.57	15.83	1.59	15.24	1.64
35	32	18.78	1.49	18.18	1.54	17.56	1.59	17.24	1.61	16.99	1.63	16.38	1.68
40	36	19.73	1.53	19.18	1.58	18.57	1.63	18.25	1.66	17.99	1.68	17.34	1.73
45	41	20.93	1.58	20.43	1.63	19.83	1.68	19.50	1.71	19.24	1.73	18.54	1.78
47	43	21.41	1.60	20.93	1.65	20.33	1.70	20.00	1.73	19.73	1.75	19.02	1.81
50	46	21.47	1.59	21.04	1.63	20.52	1.68	20.22	1.71	19.98	1.73	19.31	1.77
55	51	21.58	1.57	21.22	1.61	20.83	1.65	20.59	1.66	20.40	1.68	19.79	1.71
60	56	21.68	1.55	21.40	1.58	21.14	1.61	20.95	1.62	20.81	1.63	20.28	1.66
63	59	21.74	1.54	21.51	1.57	21.32	1.59	21.18	1.60	21.06	1.60	20.57	1.62
68	64	21.81	1.53	21.62	1.55	21.51	1.57	21.40	1.57	21.31	1.58	20.86	1.59

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Heating Capacity Tables

Heating Capacity Table for LV241HV (LUU240HV + LVN241HV4)

Table 39: Heating Capacity Table for LUU240HV + LVN241HV4.

Outdoor Air Temp.		Indoor Air Temp. °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	15.61	1.83	14.71	1.88	14.46	1.94	14.26	1.97	14.09	2.00	13.50	2.05
0	-0.4	16.75	1.85	15.89	1.91	15.56	1.97	15.32	2.00	15.13	2.03	14.51	2.08
5	4.5	18.01	1.88	17.21	1.94	16.77	2.00	16.50	2.04	16.27	2.06	15.62	2.12
10	9	19.08	1.91	18.32	1.97	17.80	2.03	17.50	2.07	17.25	2.09	16.57	2.15
17	15	20.37	1.95	19.66	2.01	19.04	2.08	18.70	2.11	18.42	2.14	17.72	2.20
20	19	21.19	1.98	20.52	2.04	19.83	2.10	19.46	2.14	19.17	2.17	18.44	2.23
25	23	22.57	2.00	21.90	2.07	21.14	2.13	20.74	2.17	20.42	2.20	19.65	2.26
30	28	23.96	2.03	23.22	2.10	22.42	2.17	22.01	2.20	21.68	2.23	20.88	2.30
35	32	25.35	2.06	24.54	2.13	23.71	2.19	23.28	2.23	22.94	2.26	22.11	2.33
40	36	26.64	2.09	25.89	2.15	25.07	2.22	24.63	2.26	24.29	2.29	23.41	2.36
45	41	28.26	2.12	27.58	2.19	26.77	2.26	26.32	2.30	25.97	2.33	25.02	2.40
47	43	28.90	2.13	28.26	2.20	27.45	2.27	27.00	2.31	26.64	2.34	25.67	2.41
50	46	28.99	2.12	28.40	2.18	27.70	2.24	27.30	2.28	26.98	2.30	26.07	2.37
55	51	29.13	2.09	28.65	2.15	28.12	2.20	27.79	2.22	27.54	2.24	26.72	2.29
60	56	29.27	2.07	28.89	2.11	28.53	2.15	28.29	2.17	28.09	2.18	27.38	2.21
63	59	29.35	2.06	29.03	2.09	28.78	2.12	28.59	2.13	28.43	2.14	27.77	2.17
68	64	29.44	2.05	29.18	2.07	29.04	2.10	28.89	2.10	28.77	2.11	28.17	2.12

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)
 PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

- All capacities are net, evaporator fan motor heat is deducted.
 - Direct interpolation is permissible.  Do not extrapolate.
- Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.
 0 ft. level difference between outdoor and indoor units.

PERFORMANCE DATA

Heating Capacity Tables

Heating Capacity Table for LV300HV (LUU360HV + LVN300HCV)

Table 40: Heating Capacity Table for LUU360HV + LVN300HCV.

Outdoor Air Temp.		Indoor Air Temp. °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	13.01	1.68	12.13	1.72	12.01	1.78	11.85	1.81	11.73	1.83	11.21	1.88
0	-0.4	15.36	1.80	14.51	1.85	14.25	1.91	14.04	1.93	13.87	1.96	13.30	2.01
5	4.5	17.98	1.93	17.14	2.00	16.73	2.06	16.46	2.09	16.24	2.11	15.59	2.18
10	9	20.21	2.07	19.39	2.13	18.85	2.20	18.52	2.23	18.26	2.26	17.55	2.32
17	15	22.88	2.24	22.09	2.31	21.39	2.39	21.00	2.42	20.69	2.46	19.90	2.52
20	19	24.48	2.33	23.71	2.40	22.92	2.47	22.49	2.51	22.14	2.55	21.31	2.62
25	23	27.15	2.38	26.34	2.45	25.43	2.53	24.94	2.58	24.56	2.61	23.63	2.69
30	28	29.79	2.46	28.87	2.54	27.88	2.62	27.37	2.67	26.96	2.70	25.97	2.78
35	32	32.40	2.50	31.38	2.58	30.31	2.67	29.76	2.72	29.32	2.75	28.27	2.83
40	36	33.85	2.54	32.90	2.62	31.85	2.71	31.29	2.76	30.85	2.79	29.74	2.87
45	41	35.67	2.60	34.82	2.69	33.80	2.78	33.23	2.82	32.78	2.86	31.59	2.95
47	43	36.40	2.63	35.58	2.71	34.56	2.80	34.00	2.85	33.55	2.89	32.33	2.97
50	46	36.50	2.61	35.77	2.68	34.88	2.76	34.37	2.81	33.97	2.84	32.83	2.92
55	51	36.68	2.58	36.07	2.64	35.40	2.71	35.00	2.74	34.67	2.76	33.65	2.82
60	56	36.86	2.55	36.38	2.61	35.93	2.65	35.62	2.67	35.38	2.68	34.48	2.73
63	59	36.97	2.53	36.56	2.57	36.24	2.61	36.00	2.63	35.80	2.64	34.97	2.68
68	64	37.07	2.52	36.75	2.55	36.57	2.58	36.38	2.59	36.23	2.60	35.47	2.61

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)
 PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

- All capacities are net, evaporator fan motor heat is deducted.
 - Direct interpolation is permissible. Ⓣ Do not extrapolate.
- Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.
 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Heating Capacity Tables

Heating Capacity Table for LV361HV (LUU360HV + LVN361HV4)

Table 41: Heating Capacity Table for LUU360HV + LVN361HV4.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	14.74	1.85	13.75	1.90	13.61	1.96	13.43	1.99	13.29	2.02	12.71	2.07
0	-0.4	17.41	1.98	16.45	2.04	16.15	2.10	15.91	2.13	15.72	2.16	15.07	2.22
5	4.5	20.38	2.13	19.43	2.20	18.96	2.27	18.66	2.30	18.41	2.33	17.67	2.40
10	9	22.90	2.28	21.98	2.35	21.36	2.42	20.99	2.46	20.70	2.49	19.89	2.56
17	15	25.93	2.47	25.03	2.55	24.24	2.63	23.80	2.67	23.45	2.71	22.55	2.78
20	19	27.85	2.60	26.97	2.68	26.07	2.76	25.58	2.81	25.19	2.85	24.24	2.93
25	23	31.07	2.72	30.15	2.81	29.10	2.90	28.55	2.95	28.11	2.99	27.05	3.08
30	28	34.31	2.89	33.25	2.98	32.11	3.07	31.52	3.13	31.05	3.17	29.91	3.26
35	32	37.55	3.01	36.36	3.11	35.12	3.21	34.49	3.27	33.98	3.31	32.76	3.41
40	36	39.47	3.14	38.36	3.24	37.14	3.35	36.49	3.41	35.98	3.45	34.68	3.55
45	41	41.86	3.30	40.86	3.41	39.66	3.52	39.00	3.58	38.47	3.63	37.07	3.74
47	43	42.82	3.37	41.86	3.48	40.66	3.59	40.00	3.65	39.47	3.70	38.03	3.81
50	46	42.94	3.34	42.08	3.44	41.04	3.54	40.44	3.60	39.97	3.64	38.62	3.74
55	51	43.15	3.31	42.44	3.39	41.65	3.47	41.18	3.51	40.79	3.54	39.59	3.62
60	56	43.36	3.27	42.80	3.34	42.27	3.40	41.91	3.42	41.62	3.44	40.56	3.50
63	59	43.49	3.25	43.01	3.30	42.64	3.35	42.35	3.37	42.12	3.39	41.14	3.43
68	64	43.61	3.23	43.23	3.27	43.02	3.31	42.80	3.32	42.62	3.33	41.73	3.35

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Heating Capacity Tables

Heating Capacity Table for LV420HV1 (LUU420HV + LVN420HV)

Table 42: Heating Capacity Table for LUU420HV + LVN420HV.

Outdoor Air Temp.		Indoor Air Temp.: °FDB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	20.39	2.67	18.93	2.76	18.79	2.84	18.57	2.88	18.38	2.92	17.57	3.00
0	-0.4	23.74	2.75	22.37	2.84	22.00	2.93	21.68	2.97	21.43	3.01	20.53	3.10
5	4.5	27.73	2.85	26.44	2.94	25.81	3.03	25.39	3.08	25.05	3.12	24.04	3.21
10	9	30.40	2.95	29.17	3.04	28.36	3.13	27.87	3.19	27.48	3.23	26.40	3.32
17	15	31.26	2.94	30.56	3.04	29.69	3.14	29.20	3.19	28.81	3.24	27.76	3.33
20	19	33.98	3.04	33.22	3.14	32.27	3.25	31.74	3.30	31.32	3.35	30.18	3.45
25	23	36.70	3.14	35.88	3.25	34.86	3.35	34.29	3.41	33.83	3.46	32.60	3.56
30	28	40.10	3.27	39.21	3.38	38.09	3.48	37.46	3.54	36.97	3.59	35.62	3.70
35	32	42.82	3.37	41.87	3.48	40.67	3.59	40.01	3.65	39.48	3.70	38.04	3.81
40	36	45.55	3.47	44.53	3.58	43.26	3.70	42.55	3.76	41.98	3.81	40.46	3.93
45	41	48.95	3.59	47.86	3.71	46.49	3.83	45.73	3.90	45.12	3.95	43.48	4.07
47	43	50.31	3.64	49.19	3.76	47.78	3.88	47.00	3.95	46.38	4.00	44.69	4.12
50	46	50.46	3.62	49.44	3.73	48.22	3.84	47.52	3.89	46.96	3.94	45.37	4.05
55	51	50.70	3.58	49.86	3.67	48.94	3.76	48.38	3.80	47.93	3.83	46.51	3.92
60	56	50.95	3.54	50.29	3.61	49.67	3.68	49.24	3.71	48.90	3.73	47.65	3.79
63	59	51.10	3.52	50.54	3.58	50.10	3.63	49.76	3.65	49.49	3.66	48.34	3.71
68	64	51.25	3.50	50.80	3.54	50.54	3.58	50.29	3.59	50.08	3.60	49.03	3.63

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible.  Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Heating Capacity Tables

Heating Capacity Table for LV420HV2 (LUU601HV + LVN420HV)

Table 43: Heating Capacity Table for LUU601HV + LVN420HV.

Outdoor Air Temp.		Indoor Air Temp.: °FDB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	30.75	3.21	28.84	3.31	28.44	3.41	28.05	3.46	27.74	3.51	26.55	3.60
0	-0.4	32.68	3.24	30.93	3.35	30.33	3.44	29.87	3.51	29.51	3.55	28.28	3.65
5	4.5	34.98	3.28	33.40	3.39	32.58	3.49	32.03	3.55	31.61	3.59	30.34	3.70
10	9	36.52	3.32	35.06	3.43	34.07	3.53	33.49	3.59	33.01	3.64	31.72	3.75
17	15	31.26	2.74	30.56	2.84	29.68	2.93	29.20	2.98	28.81	3.02	27.77	3.11
20	19	34.09	2.84	33.32	2.94	32.37	3.03	31.84	3.08	31.42	3.12	30.27	3.22
25	23	36.95	2.93	36.12	3.03	35.09	3.13	34.52	3.18	34.05	3.22	32.82	3.32
30	28	40.52	3.05	39.62	3.16	38.48	3.26	37.85	3.31	37.36	3.35	35.99	3.46
35	32	43.41	3.15	42.44	3.25	41.23	3.36	40.56	3.41	40.01	3.46	38.56	3.56
40	36	46.31	3.24	45.28	3.35	43.98	3.45	43.27	3.51	42.69	3.57	41.14	3.67
45	41	49.93	3.36	48.81	3.46	47.42	3.58	46.65	3.64	46.02	3.69	44.35	3.80
47	43	51.38	3.40	50.24	3.52	48.80	3.63	48.00	3.69	47.37	3.75	45.64	3.85
50	46	51.53	3.38	50.50	3.48	49.24	3.59	48.53	3.64	47.96	3.68	46.34	3.78
55	51	51.78	3.35	50.93	3.43	49.99	3.51	49.41	3.55	48.95	3.59	47.50	3.66
60	56	52.03	3.31	51.36	3.38	50.73	3.44	50.29	3.46	49.95	3.48	48.66	3.54
63	59	52.19	3.29	51.62	3.34	51.17	3.39	50.82	3.41	50.54	3.43	49.36	3.46
68	64	52.34	3.27	51.88	3.31	51.62	3.35	51.35	3.36	51.14	3.37	50.07	3.39

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible.  Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Heating Capacity Tables

Heating Capacity Table for LV480HV1 (LUU480HV + LVN480HV)

Table 44: Heating Capacity Table for LUU480HV + LVN480HV.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	32.43	3.62	30.42	3.73	30.00	3.84	29.59	3.90	29.26	3.95	28.01	4.06
0	-0.4	34.47	3.65	32.62	3.77	31.99	3.88	31.51	3.95	31.13	4.00	29.83	4.11
5	4.5	36.90	3.70	35.23	3.82	34.36	3.93	33.79	4.00	33.34	4.05	32.00	4.17
10	9	38.52	3.74	36.98	3.86	35.94	3.98	35.32	4.05	34.82	4.10	33.46	4.22
17	15	32.97	3.09	32.23	3.20	31.31	3.30	30.80	3.36	30.39	3.40	29.29	3.50
20	19	35.91	3.20	35.10	3.31	34.10	3.42	33.54	3.47	33.10	3.52	31.89	3.63
25	23	38.84	3.31	37.97	3.42	36.89	3.53	36.29	3.59	35.80	3.64	34.50	3.75
30	28	42.51	3.45	41.56	3.57	40.37	3.68	39.71	3.74	39.19	3.79	37.76	3.91
35	32	45.45	3.56	44.43	3.68	43.16	3.80	42.46	3.86	41.89	3.91	40.37	4.03
40	36	48.38	3.67	47.30	3.79	45.95	3.91	45.20	3.98	44.60	4.04	42.98	4.16
45	41	52.05	3.81	50.89	3.93	49.44	4.06	48.63	4.13	47.98	4.19	46.24	4.31
47	43	53.52	3.86	52.33	3.99	50.83	4.12	50.00	4.19	49.34	4.25	47.54	4.37
50	46	53.68	3.84	52.60	3.95	51.29	4.07	50.55	4.13	49.96	4.18	48.27	4.29
55	51	53.94	3.80	53.05	3.89	52.07	3.98	51.47	4.03	50.99	4.07	49.48	4.15
60	56	54.20	3.76	53.50	3.83	52.84	3.90	52.39	3.93	52.03	3.95	50.69	4.02
63	59	54.36	3.73	53.77	3.79	53.30	3.85	52.94	3.87	52.65	3.89	51.42	3.93
68	64	54.52	3.71	54.04	3.76	53.77	3.80	53.49	3.81	53.27	3.82	52.16	3.85

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Heating Capacity Tables

Heating Capacity Table for LV480HV2 (LUU601HV + LVN480HV)

Table 45: Heating Capacity Table for LUU601HV + LVN480HV.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	32.43	3.49	30.42	3.59	30.00	3.70	29.59	3.76	29.26	3.80	28.01	3.91
0	-0.4	34.47	3.51	32.62	3.63	31.99	3.74	31.51	3.80	31.13	3.85	29.83	3.96
5	4.5	36.90	3.56	35.23	3.68	34.36	3.78	33.79	3.85	33.34	3.90	32.00	4.02
10	9	38.52	3.60	36.98	3.72	35.94	3.83	35.32	3.90	34.82	3.95	33.46	4.06
17	15	32.97	2.98	32.23	3.08	31.31	3.18	30.80	3.24	30.39	3.27	29.29	3.37
20	19	35.91	3.07	35.10	3.17	34.10	3.28	33.54	3.33	33.10	3.37	31.89	3.48
25	23	38.84	3.15	37.97	3.25	36.89	3.36	36.29	3.41	35.80	3.46	34.50	3.57
30	28	42.51	3.25	41.56	3.37	40.37	3.47	39.71	3.53	39.19	3.58	37.76	3.69
35	32	45.45	3.33	44.43	3.44	43.16	3.56	42.46	3.61	41.89	3.66	40.37	3.77
40	36	48.38	3.41	47.30	3.52	45.95	3.63	45.20	3.70	44.60	3.75	42.98	3.86
45	41	52.05	3.51	50.89	3.62	49.44	3.74	48.63	3.80	47.98	3.86	46.24	3.97
47	43	53.52	3.54	52.33	3.66	50.83	3.78	50.00	3.85	49.34	3.90	47.54	4.01
50	46	53.68	3.52	52.60	3.63	51.29	3.74	50.55	3.79	49.96	3.84	48.27	3.94
55	51	53.94	3.49	53.05	3.57	52.07	3.65	51.47	3.70	50.99	3.74	49.48	3.81
60	56	54.20	3.45	53.50	3.52	52.84	3.58	52.39	3.61	52.03	3.63	50.69	3.69
63	59	54.36	3.42	53.77	3.48	53.30	3.53	52.94	3.55	52.65	3.57	51.42	3.61
68	64	54.52	3.41	54.04	3.45	53.77	3.49	53.49	3.50	53.27	3.51	52.16	3.53

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Heating Capacity Tables

Heating Capacity Table for LV600HV (LUU601HV + LVN600HV)

Table 46: Heating Capacity Table for LUU601HV + LVN600HV.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	37.91	4.55	35.56	4.69	35.06	4.82	34.59	4.90	34.20	4.96	32.74	5.10
0	-0.4	40.29	4.58	38.13	4.74	37.39	4.87	36.83	4.96	36.39	5.02	34.87	5.16
5	4.5	43.13	4.65	41.18	4.80	40.16	4.94	39.49	5.02	38.97	5.09	37.40	5.24
10	9	45.02	4.70	43.22	4.85	42.01	5.00	41.28	5.09	40.70	5.15	39.11	5.30
17	15	38.54	3.88	37.67	4.02	36.60	4.15	36.00	4.22	35.52	4.27	34.24	4.40
20	19	41.83	3.98	40.89	4.12	39.72	4.25	39.07	4.31	38.56	4.38	37.15	4.51
25	23	45.00	4.05	43.99	4.18	42.74	4.31	42.04	4.39	41.47	4.45	39.97	4.58
30	28	48.97	4.14	47.88	4.29	46.51	4.42	45.75	4.49	45.15	4.55	43.50	4.70
35	32	52.06	4.20	50.90	4.34	49.44	4.48	48.64	4.55	47.99	4.61	46.25	4.75
40	36	55.11	4.25	53.88	4.39	52.34	4.53	51.49	4.61	50.80	4.68	48.96	4.82
45	41	58.95	4.33	57.64	4.47	56.00	4.62	55.08	4.70	54.34	4.77	52.37	4.90
47	43	60.48	4.36	59.13	4.51	57.44	4.65	56.50	4.73	55.75	4.80	53.72	4.93
50	46	60.66	4.34	59.44	4.46	57.96	4.60	57.12	4.66	56.45	4.72	54.55	4.84
55	51	60.95	4.29	59.95	4.39	58.84	4.49	58.16	4.55	57.62	4.60	55.91	4.69
60	56	61.25	4.25	60.46	4.32	59.71	4.40	59.20	4.44	58.79	4.46	57.28	4.54
63	59	61.43	4.21	60.76	4.28	60.23	4.35	59.82	4.37	59.49	4.39	58.10	4.44
68	64	61.61	4.19	61.07	4.25	60.76	4.29	60.44	4.30	60.20	4.31	58.94	4.35

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Maximum Heating Capacity Tables

Maximum Heating Capacity Table for LV181HV (LUU180HV + LVN181HV4)

Table 47: Maximum Heating Capacity Table for LUU180HV + LVN181HV4.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	21.31	2.70	20.83	2.79	20.24	2.87	19.91	2.92	19.64	2.96	18.93	3.05
0	-0.4	21.59	2.80	21.11	2.89	20.51	2.98	20.17	3.03	19.90	3.07	19.18	3.16
5	4.5	17.34	2.17	16.95	2.24	16.47	2.31	16.20	2.35	15.98	2.38	15.40	2.45
10	9	19.54	2.34	19.11	2.42	18.56	2.49	18.26	2.54	18.01	2.57	17.36	2.65
17	15	22.48	2.46	21.98	2.54	21.35	2.62	21.00	2.67	20.72	2.71	19.97	2.79
20	19	22.94	2.42	22.43	2.50	21.78	2.58	21.43	2.63	21.14	2.66	20.37	2.74
25	23	23.40	2.38	22.87	2.46	22.22	2.54	21.86	2.58	21.57	2.62	20.78	2.70
30	28	23.97	2.33	23.43	2.41	22.76	2.49	22.39	2.53	22.10	2.57	21.29	2.64
35	32	24.43	2.29	23.88	2.37	23.20	2.45	22.82	2.49	22.52	2.52	21.70	2.60
40	36	24.89	2.25	24.33	2.33	23.64	2.40	23.25	2.45	22.94	2.48	22.11	2.55
45	41	25.46	2.21	24.89	2.28	24.18	2.35	23.79	2.39	23.47	2.42	22.62	2.50
47	43	25.69	2.19	25.12	2.26	24.40	2.33	24.00	2.35	23.68	2.40	22.82	2.47
50	46	25.77	2.17	25.25	2.24	24.62	2.30	24.26	2.34	23.98	2.36	23.17	2.43
55	51	25.89	2.15	25.46	2.20	24.99	2.25	24.71	2.28	24.48	2.30	23.75	2.35
60	56	26.02	2.13	25.68	2.17	25.36	2.21	25.15	2.22	24.97	2.24	24.33	2.27
63	59	26.09	2.11	25.81	2.15	25.59	2.18	25.41	2.19	25.27	2.20	24.68	2.22
68	64	26.17	2.10	25.94	2.13	25.81	2.15	25.68	2.16	25.57	2.16	25.04	2.18

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

- All capacities are net, evaporator fan motor heat is deducted.
- Direct interpolation is permissible. ⚠ Do not extrapolate.
- Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Maximum Heating Capacity Tables

Maximum Heating Capacity Table for LV241HV (LUU240HV + LVN241HV4)

Table 48: Maximum Heating Capacity Table for LUU240HV + LVN241HV4.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	22.22	2.86	21.73	2.95	21.11	3.05	20.76	3.10	20.49	3.14	19.74	3.23
0	-0.4	23.57	2.97	23.05	3.06	22.39	3.16	22.02	3.21	21.73	3.26	20.94	3.35
5	4.5	22.91	2.69	22.40	2.78	21.76	2.87	21.40	2.92	21.12	2.96	20.35	3.05
10	9	25.02	2.74	24.46	2.83	23.76	2.92	23.37	2.97	23.06	3.01	22.22	3.10
17	15	27.83	2.77	27.21	2.86	26.43	2.95	26.00	3.00	25.65	3.04	24.72	3.13
20	19	28.44	2.78	27.81	2.87	27.01	2.96	26.57	3.02	26.22	3.06	25.26	3.15
25	23	29.05	2.80	28.41	2.89	27.59	2.98	27.14	3.03	26.78	3.07	25.81	3.16
30	28	29.82	2.81	29.15	2.91	28.32	3.00	27.86	3.05	27.49	3.09	26.49	3.19
35	32	30.43	2.83	29.75	2.92	28.90	3.01	28.43	3.07	28.05	3.11	27.03	3.20
40	36	31.04	2.84	30.35	2.94	29.48	3.03	29.00	3.08	28.61	3.12	27.57	3.22
45	41	31.81	2.86	31.10	2.96	30.21	3.05	29.71	3.10	29.32	3.14	28.25	3.24
47	43	32.11	2.87	31.40	2.96	30.50	3.06	30.00	3.11	29.60	3.15	28.52	3.25
50	46	32.21	2.85	31.56	2.94	30.78	3.02	30.33	3.07	29.97	3.10	28.96	3.19
55	51	32.36	2.82	31.83	2.89	31.24	2.96	30.88	2.99	30.59	3.02	29.69	3.08
60	56	32.52	2.79	32.10	2.84	31.70	2.90	31.43	2.92	31.22	2.93	30.42	2.98
63	59	32.62	2.77	32.26	2.82	31.98	2.86	31.76	2.87	31.59	2.88	30.85	2.92
68	64	32.71	2.75	32.42	2.79	32.26	2.82	32.10	2.83	31.96	2.83	31.30	2.86

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. Ⓣ Do not extrapolate.

3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Maximum Heating Capacity Tables

Maximum Heating Capacity Table for LV300HV (LUU360HV + LVN300HCV)

Table 49: Maximum Heating Capacity Table for LUU360HV + LVN300HCV.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	33.27	4.70	32.52	4.85	31.60	5.00	31.08	5.09	30.66	5.15	29.55	5.31
0	-0.4	34.54	4.87	33.77	5.04	32.80	5.19	32.27	5.28	31.84	5.35	30.68	5.51
5	4.5	34.90	4.89	34.11	5.06	33.14	5.22	32.60	5.31	32.17	5.38	31.00	5.54
10	9	35.96	4.54	35.15	4.69	34.15	4.85	33.59	4.93	33.14	5.00	31.93	5.15
17	15	37.27	4.23	36.44	4.36	35.39	4.51	34.81	4.58	34.35	4.65	33.10	4.78
20	19	37.74	4.10	36.90	4.24	35.84	4.37	35.26	4.45	34.79	4.51	33.52	4.64
25	23	37.98	3.94	37.13	4.07	36.07	4.20	35.47	4.27	35.01	4.33	33.74	4.46
30	28	38.38	3.77	37.52	3.89	36.46	4.02	35.85	4.08	35.38	4.14	34.10	4.26
35	32	38.57	3.61	37.71	3.73	36.63	3.84	36.03	3.91	35.55	3.97	34.26	4.09
40	36	38.73	3.45	37.86	3.57	36.79	3.68	36.19	3.75	35.70	3.80	34.40	3.91
45	41	39.06	3.30	38.19	3.40	37.09	3.51	36.49	3.57	36.00	3.62	34.69	3.73
47	43	39.18	3.23	38.30	3.34	37.20	3.44	36.60	3.50	36.11	3.55	34.80	3.66
50	46	39.29	3.20	38.50	3.30	37.54	3.40	37.00	3.45	36.57	3.49	35.33	3.59
55	51	39.49	3.17	38.83	3.25	38.12	3.33	37.67	3.37	37.32	3.40	36.22	3.47
60	56	39.67	3.14	39.16	3.20	38.68	3.26	38.34	3.28	38.08	3.30	37.11	3.35
63	59	39.79	3.12	39.36	3.17	39.02	3.22	38.75	3.23	38.54	3.24	37.64	3.28
68	64	39.91	3.10	39.55	3.14	39.36	3.17	39.16	3.19	39.00	3.19	38.18	3.22

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.
2. Direct interpolation is permissible. ⚠ Do not extrapolate.
3. Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Maximum Heating Capacity Tables

Maximum Heating Capacity Table for LV361HV (LUU360HV + LVN361HV4)

Table 50: Maximum Heating Capacity Table for LUU360HV + LVN361HV4.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	34.49	4.84	33.72	5.00	32.76	5.15	32.22	5.24	31.79	5.31	30.64	5.47
0	-0.4	35.81	5.02	35.01	5.19	34.01	5.35	33.46	5.44	33.01	5.51	31.81	5.68
5	4.5	36.18	5.04	35.37	5.21	34.36	5.38	33.80	5.47	33.35	5.54	32.14	5.71
10	9	37.81	4.79	36.96	4.95	35.91	5.11	35.32	5.20	34.85	5.27	33.58	5.43
17	15	39.98	4.61	39.09	4.76	37.97	4.92	37.35	5.00	36.85	5.07	35.51	5.22
20	19	40.84	4.54	39.93	4.69	38.79	4.84	38.16	4.93	37.65	4.99	36.28	5.14
25	23	41.71	4.47	40.78	4.62	39.61	4.77	38.96	4.85	38.45	4.92	37.05	5.07
30	28	42.79	4.39	41.83	4.53	40.64	4.68	39.97	4.76	39.44	4.82	38.01	4.97
35	32	43.65	4.32	42.68	4.46	41.46	4.60	40.78	4.68	40.24	4.75	38.78	4.89
40	36	44.52	4.25	43.52	4.39	42.28	4.53	41.59	4.61	41.03	4.67	39.54	4.81
45	41	45.60	4.17	44.58	4.30	43.30	4.44	42.60	4.52	42.03	4.58	40.50	4.72
47	43	46.03	4.13	45.00	4.27	43.71	4.40	43.00	4.48	42.43	4.54	40.89	4.68
50	46	46.16	4.10	45.23	4.23	44.11	4.35	43.47	4.42	42.96	4.47	41.51	4.59
55	51	46.39	4.06	45.62	4.16	44.78	4.26	44.26	4.31	43.85	4.35	42.55	4.44
60	56	46.61	4.02	46.01	4.10	45.44	4.17	45.05	4.20	44.74	4.23	43.60	4.29
63	59	46.75	3.99	46.24	4.06	45.84	4.12	45.53	4.14	45.28	4.15	44.22	4.20
68	64	46.89	3.97	46.47	4.02	46.24	4.06	46.01	4.08	45.82	4.08	44.86	4.12

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

- All capacities are net, evaporator fan motor heat is deducted.
- Direct interpolation is permissible. ⚠ Do not extrapolate.
- Grey shading indicates reference data. When operating the unit at this temperature, these values can be different by discontinuous operation.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Maximum Heating Capacity Tables

Maximum Heating Capacity Table for LV420HV1 (LUU420HV + LVN420HV)

Table 51: Maximum Heating Capacity Table for LUU420HV + LVN420HV.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	35.21	4.17	34.42	4.31	33.44	4.45	32.89	4.53	32.45	4.59	31.27	4.73
0	-0.4	36.78	4.34	35.96	4.48	34.93	4.62	34.36	4.70	33.90	4.77	32.67	4.91
5	4.5	41.21	5.53	40.29	5.72	39.14	5.90	38.50	6.00	37.99	6.08	36.61	6.26
10	9	41.44	5.00	40.51	5.16	39.36	5.33	38.71	5.42	38.20	5.49	36.81	5.66
17	15	41.75	4.61	40.81	4.76	39.65	4.92	39.00	5.00	38.48	5.07	37.08	5.22
20	19	44.19	4.70	43.21	4.85	41.97	5.01	41.29	5.09	40.74	5.16	39.26	5.32
25	23	46.64	4.78	45.60	4.94	44.30	5.10	43.57	5.19	42.99	5.26	41.43	5.41
30	28	49.70	4.89	48.59	5.05	47.20	5.21	46.43	5.30	45.81	5.37	44.15	5.54
35	32	52.15	4.97	50.98	5.14	49.52	5.30	48.71	5.39	48.07	5.47	46.32	5.63
40	36	54.59	5.06	53.37	5.23	51.85	5.39	51.00	5.49	50.32	5.56	48.49	5.73
45	41	57.65	5.17	56.36	5.34	54.75	5.51	53.86	5.60	53.14	5.68	51.21	5.85
47	43	58.87	5.21	57.56	5.38	55.91	5.55	55	5.65	54.27	5.73	52.30	5.90
50	46	59.05	5.18	57.86	5.33	56.42	5.49	55.61	5.57	54.95	5.64	53.10	5.79
55	51	59.33	5.12	58.35	5.25	57.27	5.37	56.62	5.43	56.09	5.48	54.43	5.60
60	56	59.62	5.07	58.85	5.17	58.12	5.26	57.63	5.30	57.23	5.33	55.76	5.41
63	59	59.80	5.03	59.14	5.12	58.63	5.19	58.23	5.22	57.91	5.24	56.56	5.30
68	64	59.97	5.00	59.44	5.07	59.15	5.13	58.84	5.14	58.60	5.15	57.38	5.19

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.
2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Maximum Heating Capacity Tables

Maximum Heating Capacity Table for LV420HV2 (LUU601HV + LVN420HV)

Table 52: Maximum Heating Capacity Table for LUU601HV + LVN420HV.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	35.79	3.91	34.99	4.04	33.98	4.17	33.44	4.23	32.99	4.30	31.79	4.42
0	-0.4	37.61	4.05	36.77	4.19	35.72	4.32	35.14	4.40	34.67	4.45	33.41	4.59
5	4.5	42.82	5.14	41.86	5.32	40.67	5.49	40.00	5.58	39.47	5.65	38.04	5.82
10	9	42.29	4.79	41.35	4.95	40.16	5.11	39.51	5.20	38.99	5.26	37.57	5.43
17	15	41.54	4.50	40.60	4.65	39.44	4.80	38.80	4.88	38.29	4.95	36.89	5.10
20	19	44.01	4.56	43.03	4.71	41.80	4.86	41.12	4.94	40.57	5.02	39.09	5.17
25	23	46.07	4.60	45.04	4.75	43.75	4.90	43.04	4.99	42.47	5.05	40.93	5.20
30	28	48.74	4.65	47.65	4.80	46.28	4.96	45.53	5.04	44.92	5.11	43.29	5.26
35	32	50.57	4.68	49.44	4.83	48.03	4.99	47.24	5.07	46.61	5.14	44.92	5.30
40	36	52.29	4.70	51.13	4.86	49.66	5.01	48.85	5.10	48.20	5.17	46.45	5.33
45	41	54.58	4.75	53.36	4.90	51.83	5.06	50.98	5.15	50.30	5.22	48.48	5.37
47	43	55.45	4.77	54.21	4.93	52.66	5.09	51.80	5.17	51.11	5.24	49.25	5.40
50	46	55.61	4.74	54.49	4.88	53.14	5.02	52.37	5.09	51.76	5.15	50.00	5.30
55	51	55.88	4.69	54.96	4.80	53.94	4.92	53.32	4.97	52.83	5.02	51.26	5.13
60	56	56.15	4.64	55.43	4.73	54.74	4.81	54.27	4.85	53.90	4.88	52.52	4.95
63	59	56.32	4.60	55.70	4.68	55.22	4.75	54.85	4.78	54.55	4.79	53.28	4.85
68	64	56.48	4.58	55.99	4.64	55.70	4.69	55.42	4.70	55.19	4.71	54.04	4.75

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Maximum Heating Capacity Tables

Maximum Heating Capacity Table for LV480HV1 (LUU480HV + LVN480HV)

Table 53: Maximum Heating Capacity Table for LUU480HV + LVN480HV.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	35.34	4.20	34.55	4.34	33.56	4.48	33.02	4.55	32.58	4.62	31.39	4.75
0	-0.4	37.14	4.36	36.31	4.51	35.27	4.65	34.70	4.73	34.24	4.79	32.99	4.94
5	4.5	42.28	5.53	41.34	5.72	40.16	5.90	39.50	6.00	38.98	6.08	37.56	6.26
10	9	42.51	5.22	41.56	5.39	40.37	5.56	39.71	5.66	39.19	5.73	37.76	5.91
17	15	42.82	4.99	41.86	5.15	40.66	5.32	40.00	5.41	39.47	5.48	38.03	5.65
20	19	45.88	5.09	44.85	5.26	43.57	5.43	42.86	5.52	42.29	5.60	40.75	5.77
25	23	48.93	5.20	47.84	5.37	46.47	5.54	45.71	5.64	45.11	5.71	43.47	5.88
30	28	52.76	5.33	51.58	5.50	50.10	5.68	49.29	5.78	48.63	5.86	46.86	6.03
35	32	55.82	5.43	54.57	5.61	53.01	5.79	52.14	5.89	51.45	5.97	49.58	6.15
40	36	58.87	5.53	57.56	5.72	55.91	5.90	55.00	6.00	54.27	6.08	52.30	6.27
45	41	62.70	5.66	61.30	5.85	59.54	6.04	58.57	6.14	57.79	6.23	55.69	6.41
47	43	64.23	5.72	62.79	5.91	61.00	6.10	60	6.2	59.20	6.28	57.05	6.47
50	46	64.41	5.68	63.12	5.85	61.55	6.02	60.66	6.11	59.95	6.18	57.92	6.35
55	51	64.73	5.62	63.66	5.76	62.48	5.90	61.76	5.96	61.19	6.02	59.38	6.15
60	56	65.04	5.56	64.20	5.67	63.41	5.77	62.86	5.82	62.43	5.85	60.83	5.94
63	59	65.23	5.52	64.52	5.61	63.96	5.70	63.53	5.73	63.18	5.75	61.71	5.82
68	64	65.42	5.49	64.85	5.56	64.52	5.62	64.19	5.64	63.93	5.65	62.59	5.70

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.
2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Maximum Heating Capacity Tables

Maximum Heating Capacity Table for LV480HV2 (LUU601HV + LVN480HV)

Table 54: Maximum Heating Capacity Table for LUU601HV + LVN480HV.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	36.23	3.96	35.42	4.09	34.41	4.22	33.86	4.28	33.40	4.35	32.18	4.47
0	-0.4	38.08	4.11	37.23	4.25	36.16	4.38	35.58	4.45	35.11	4.51	33.83	4.65
5	4.5	43.35	5.21	42.39	5.39	41.18	5.56	40.50	5.65	39.97	5.73	38.51	5.89
10	9	42.95	4.87	41.99	5.03	40.79	5.19	40.12	5.28	39.60	5.35	38.15	5.51
17	15	42.37	4.60	41.42	4.74	40.23	4.90	39.58	4.98	39.06	5.05	37.63	5.20
20	19	44.99	4.66	43.98	4.82	42.72	4.97	42.03	5.06	41.47	5.13	39.96	5.28
25	23	47.25	4.72	46.20	4.87	44.87	5.03	44.14	5.12	43.56	5.18	41.98	5.33
30	28	50.16	4.79	49.04	4.94	47.63	5.10	46.86	5.19	46.23	5.27	44.55	5.42
35	32	52.24	4.83	51.07	4.99	49.61	5.15	48.79	5.24	48.15	5.31	46.40	5.47
40	36	54.21	4.87	53.01	5.04	51.49	5.20	50.65	5.29	49.98	5.36	48.16	5.53
45	41	56.80	4.94	55.54	5.11	53.94	5.27	53.06	5.36	52.36	5.44	50.45	5.59
47	43	57.81	4.97	56.51	5.14	54.90	5.30	54.00	5.39	53.28	5.46	51.35	5.62
50	46	57.97	4.94	56.81	5.09	55.40	5.23	54.59	5.31	53.96	5.37	52.13	5.52
55	51	58.26	4.89	57.29	5.01	56.23	5.13	55.58	5.18	55.07	5.23	53.44	5.35
60	56	58.54	4.83	57.78	4.93	57.07	5.02	56.57	5.06	56.19	5.09	54.75	5.16
63	59	58.71	4.80	58.07	4.88	57.56	4.96	57.18	4.98	56.86	5.00	55.54	5.06
68	64	58.88	4.77	58.37	4.83	58.07	4.89	57.77	4.90	57.54	4.91	56.33	4.96

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping. 0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

PERFORMANCE DATA

Maximum Heating Capacity Tables

Maximum Heating Capacity Table for LV600HV (LUU601HV + LVN600HV)

Table 55: Maximum Heating Capacity Table for LUU601HV + LVN600HV.

Outdoor Air Temp.		Indoor Air Temp.: °F DB											
		61.0		64.0		68.0		70.0		72.0		75.0	
°F DB	°F WB	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI	TC	PI
-4	-4.4	37.13	4.73	36.30	4.89	35.26	5.05	34.69	5.13	34.23	5.21	32.98	5.35
0	-0.4	39.02	4.91	38.15	5.08	37.06	5.24	36.46	5.33	35.97	5.40	34.66	5.57
5	4.5	44.42	6.23	43.43	6.44	42.19	6.65	41.50	6.76	40.95	6.85	39.46	7.05
10	9	44.49	5.84	43.50	6.03	42.25	6.23	41.56	6.34	41.02	6.42	39.52	6.62
17	15	44.57	5.54	43.57	5.72	42.32	5.90	41.64	6.00	41.09	6.08	39.59	6.27
20	19	47.65	5.63	46.58	5.82	45.25	6.00	44.51	6.10	43.92	6.19	42.32	6.38
25	23	50.62	5.71	49.49	5.90	48.07	6.09	47.29	6.20	46.66	6.27	44.97	6.46
30	28	54.36	5.82	53.15	6.00	51.62	6.20	50.79	6.31	50.11	6.40	48.29	6.58
35	32	57.29	5.89	56.01	6.08	54.41	6.28	53.52	6.39	52.81	6.47	50.89	6.67
40	36	60.18	5.96	58.85	6.16	57.16	6.36	56.23	6.47	55.48	6.55	53.47	6.76
45	41	63.85	6.06	62.42	6.26	60.63	6.47	59.64	6.57	58.85	6.67	56.71	6.86
47	43	65.30	6.11	63.84	6.31	62.02	6.51	61.00	6.62	60.19	6.71	58.00	6.91
50	46	65.48	6.06	64.17	6.25	62.58	6.43	61.67	6.52	60.95	6.60	58.89	6.78
55	51	65.81	6.00	64.72	6.15	63.52	6.30	62.79	6.36	62.21	6.43	60.37	6.57
60	56	66.12	5.94	65.27	6.05	64.47	6.16	63.91	6.21	63.47	6.25	61.84	6.34
63	59	66.32	5.89	65.60	5.99	65.03	6.09	64.59	6.12	64.23	6.14	62.74	6.21
68	64	66.51	5.86	65.93	5.94	65.60	6.00	65.26	6.02	65.00	6.03	63.63	6.09

DB: Dry Bulb Temperature (°F) WB: Wet Bulb Temperature (°F) TC: Total Capacity (kBtu/h)

PI: Power Input (kW) (includes compressor, indoor fan motor, and outdoor fan motor)

1. All capacities are net, evaporator fan motor heat is deducted.

2. Direct interpolation is permissible. ⚠ Do not extrapolate.

Nominal capacity as rated: 0 ft. above sea level with 25 ft. of refrigerant piping.

0 ft. level difference between outdoor and indoor units.

Nominal heating capacity rating obtained with air entering the indoor unit at 70°F dry bulb (DB) and 60°F wet bulb (WB), and outdoor ambient conditions of 47°F dry bulb (DB) and 43°F wet bulb (WB).

EQUIPMENT SELECTION PROCEDURE

Correction Factors

Cooling / Heating Correction Factors

For Single Zone Vertical Air Handling Unit systems, calculate the equivalent length of the liquid line from the outdoor unit to the indoor unit. Also, determine the elevation difference of the indoor unit above or below the outdoor unit. Find corresponding cooling or heating capacity correction factors as shown below. Multiply the correction factors by the cooling or heating capacity obtained from the capacity table using design conditions. The result is the NET cooling or heating capacity.

Refrigerant Line Length Derates

For air-cooled systems, a capacity correction factor may have to be applied to account for the length of the system's refrigerant pipe. Rate of change in capacity due to increased piping lengths is shown below.

Cooling Capacity Coefficient Factors

Table 56: Vertical Air Handling Unit Cooling Capacity Coefficient Factors.

Piping Length (ft.)		24.6	32.8	49.2	65.6	98.4	131.2	164	196.9	229.7	246
Rate of Capacity Change (%)	LUU180HV (18,000 Btu/h)	100	100	99.3	97.9	96.6	93.8	91.1	-	-	-
	LUU240HV (24,000 Btu/h)	100	100	99.3	97.9	96.6	93.8	91.1	-	-	-
	LUU360HV (36,000 Btu/h)	100	100	99.3	97.9	96.6	93.8	91.1	88.4	85.6	82.9
	LUU420HV (42,000 Btu/h)	100	99.3	97.9	96.6	93.8	91.1	88.4	85.6	82.9	81.5
	LUU480HV (48,000 Btu/h)	100	99.3	97.9	96.6	93.8	91.1	88.4	85.6	82.9	81.5
	LUU601HV (60,000 Btu/h)	100	99.3	97.9	96.6	93.8	91.1	88.4	85.6	82.9	81.5

Heating Capacity Coefficient Factors

Table 57: Vertical Air Handling Unit Heating Capacity Coefficient Factors.

Piping Length (ft.)		24.6	32.8	49.2	65.6	98.4	131.2	164	196.9	229.7	246
Rate of Capacity Change (%)	LUU180HV (18,000 Btu/h)	100	99.3	97.9	96.6	9.8	91.1	88.4	-	-	-
	LUU240HV (24,000 Btu/h)	100	99.3	97.9	96.6	9.8	91.1	88.4	-	-	-
	LUU360HV (36,000 Btu/h)	100	99.7	99.2	98.7	97.7	96.6	95.6	94.6	93.5	93.0
	LUU420HV (42,000 Btu/h)	100	99.7	99.2	98.7	97.7	96.6	95.6	94.6	93.5	93.0
	LUU480HV (48,000 Btu/h)	100	99.7	99.2	98.7	97.7	96.6	95.6	94.6	93.5	93.0
	LUU601HV (60,000 Btu/h)	100	99.7	99.2	98.7	97.7	96.6	95.6	94.6	93.5	93.0

EQUIPMENT SELECTION PROCEDURE

Correction Factors

Equivalent Piping Length for Piping Components

Table 58: Equivalent Piping Length for Elbows.

Component	Size (Inches)													
	1/4	3/8	1/2	5/8	3/4	7/8	1	1-1/8	1-1/4	1-3/8	1-1/2	1-5/8	1-3/4	2-1/8
Elbow (ft.)	0.5	0.6	0.7	0.8	1.2	1.3	1.5	1.6	1.8	2.0	2.1	2.3	2.5	2.8

Altitude Correction Factor

The impact of air density must be considered on systems installed at a significant altitude above sea level, therefore, locally accepted altitude correction factors must be applied.

Defrost Correction Factor for Heating Operation

The outdoor unit heating capacity may need to be adjusted for frost accumulation on air-cooled systems. If design day conditions are below the dewpoint of the surrounding air, frost may not be a problem and no correction factor is needed. In certain weather conditions, however, frost may form and accumulate on the air-cooled outdoor unit coil and impact the coils ability to transfer heat. If significant frost accumulates on the outdoor unit coil, a defrost algorithm will start automatically. The timing between defrost periods is determined by the system's ability to achieve a target head pressure value.

Capacity and AHRI ratings tables do not factor in capacity reduction when frost has accumulated on the condenser coil, nor during defrost operation.

Integrated heating capacity values can be obtained using the formula: **Table 59: Outdoor Unit Frost Accumulation Factor (Heating)¹.**

$$A = B \times C$$

Where:

A = Integrated Heating Capacity.

B = Value found in the Capacity Table.

C = Correction Factor for Frost Accumulation Factor (from table at right).

Entering DB (°F)	19.4	23.0	26.6	32.0	37.4	41.0	44.6
Derate factor	0.98	0.95	0.93	0.86	0.93	0.96	1.0

¹At 85% outdoor air relative humidity.

The frost accumulation factor does not account for effects of snow accumulation restricting airflow through the outdoor unit coil.

Note:

There will be a temporary reduction in capacity when frost / ice accumulates on the outside surface of the outdoor unit heat exchanger. The level of capacity reduction depends on a number of factors, for example, outdoor temperature (°F DB), relative humidity (RH), and the amount of frost present.

EQUIPMENT SELECTION PROCEDURE

Check the Indoor and Outdoor Unit Selection(s)

Compare the corrected cooling and heating capacities to the load calculations. Is each capacity sufficient for the zone it serves?

For each indoor unit, the corrected capacity must be at least equal to the total of the cooling design load (plus ventilation load, if applicable) for the space served by the indoor unit. For each indoor unit, the corrected capacity also must be at least equal to the total of the heating design load (plus ventilation load, if applicable) for the space(s) and / or thermal zones served by the indoor unit.

The outdoor unit selected must be large enough to offset the total cooling load for all spaces it serves (account for ventilation air cooling load if the ventilation air has not been pretreated to room neutral conditions). The outdoor unit must also be large enough to offset the total heating load for all spaces it serves.

If the corrected heating capacity ratio exceeds 100%, reselect the equipment, or change the system design by moving some of the load to another system.

System Sizing Check Formulas

1. Outdoor Unit Rated Capacity.

$Q_{\text{odu(rated)}}$ (From capacity tables).

2. Outdoor Unit Capacity at T_i , T_o Temperature.

$Q_{\text{odu}(T_i, T_o)}$ (From capacity tables).

3 Outdoor Unit Capacity Coefficient Factor.

$F_{(T_i, T_o)} = Q_{\text{odu}(T_i, T_o)} / Q_{\text{odu(rated)}}$

4. Piping Correction Factor (From Capacity Coefficient Factor Tables).

$F_{(\text{length})}$ for each piping length

5. Individual Indoor Unit Combination Capacity.

$Q_{\text{idu (combi)}} = Q_{\text{odu(rated)}} \times Q_{\text{idu(rated)}} / Q_{\text{idu(rated-total)}}$

6. Individual Indoor Unit Actual Capacity.

$Q_{\text{idu (actual)}} = Q_{\text{odu(combi)}} \times F_{(T_i, T_o)} \times F_{(\text{length, altitude})}$

Conclusions and Recommendations

- Understand the design safety factors.
- Reference load calculations for actual cooling and heating capacities (applies in 99% of applications – consider total load when latent load is greater than 30%).
- Verify that the sensible load of the zone is satisfied.
- Use caution when sizing to meet listed capacity specifications for the scheduled manufacturer's equipment.

If further system design assistance is needed, or you have a unique application you would like to discuss, contact your LG sales rep.

VERTICAL AIR HANDLING UNIT APPLICATION GUIDELINES

Placement Considerations on page 93

Clearances on page 97

Installing Outdoor Units Indoors on page 100

Refrigerant Piping Design on page 102

PLACEMENT CONSIDERATIONS

Indoor Unit

Selecting the Best Location for the Indoor Unit

Dos

- Place the unit where air circulation will not be blocked.
- Place the unit where drainage can be obtained easily and to minimize the length of the condensate drain piping.
- Place the unit where noise prevention is taken into consideration.
- Place the unit in a location that can support the indoor unit weight, and where the indoor unit can be level.
- The mounting floor must be strong and solid enough to prevent the indoor unit from vibrating.
- Ensure there is sufficient maintenance and clearance space (wall, ceiling, or other obstacles; see diagram for clearances).
- Locate the indoor unit in a location where it can be easily connected to the outdoor unit.



Don'ts

- Avoid installing the unit near high-frequency generators.
- No obstacles must be present to prevent indoor unit air circulation.
- Do not install the unit near a doorway.
- Do not install the unit near a heat or steam source, or where considerable amounts of oil, iron powder, or flour are used. (These materials may generate condensate, cause a reduction in heat exchanger efficiency, or the drain pump to malfunction. If this is a potential problem, install a ventilation fan large enough to vent out these materials.)

WARNING

The unit must not be installed where sulfuric acid and flammable or corrosive gases are generated, vented into, or stored. There is risk of fire, explosion, and physical injury or death.

The unit may be damaged, may malfunction, and / or will not operate as designed if installed in any of the conditions listed.

Note:

Indoor units (IDUs) must not be placed in an environment where the IDUs may be exposed to harmful volatile organic compounds (VOCs) or in environments where there is improper air make up or supply or inadequate ventilation. If there are concerns about VOCs in the environment where the IDUs are installed, proper air make up or supply and/ or adequate ventilation must be provided. Additionally, in buildings where IDUs will be exposed to VOCs, consider a factory-applied epoxy coating to the fan coils for each IDU.

If the unit is installed near a body of water, the installation parts are at risk of corroding. Appropriate anti-corrosion methods must be taken for the unit and all installation parts.

Installing in an Area Exposed to Unconditioned Air

In some installation applications, areas (floors, walls) in some rooms may be exposed to unconditioned air (room may be above or next to an unheated garage or storeroom). To countermeasure:

- Verify that carpet is or will be installed (carpet may increase the temperature by three [3] degrees).
- Add insulation between the floor joists.
- Install radiant heat or another type of heating system to the floor.

Figure 58: Recommended Clearances for Vertical Air Handling Unit IDU.





Figure 59: Installing Near a Heat or Steam Source.



PLACEMENT CONSIDERATIONS

Outdoor Unit

Selecting the Best Location for the Outdoor Unit

⚠ DANGER

- ⊘ Do not install the unit in an area where combustible gas may generate, flow, stagnate, or leak. These conditions can cause a fire, resulting in bodily injury or death.
- ⊘ Do not install the unit in a location where acidic solution and spray (sulfur) are often used as it can cause bodily injury or death.
- ⊘ Do not use the unit in environments where oil, steam, or sulfuric gas are present as it can cause bodily injury or death.

⚠ WARNING

When deciding on a location to place the outdoor unit, be sure to choose an area where run-off from defrost will not accumulate and freeze on sidewalks or driveways, which may create unsafe conditions. Properly install and insulate any drain hoses to prevent the hose from freezing, cracking, leaking, and causing unsafe conditions from frozen condensate.

Install a fence to prevent vermin from crawling into the unit or unauthorized individuals from accessing it. Follow the placement guidelines set forth in "Clearance Requirements".

Select a location for installing the outdoor unit that will meet the following conditions:

- Where there is enough strength to bear the weight of the outdoor unit.
- A location that allows for optimum air flow and is easily accessible for inspection, maintenance, and service.
- Where piping between the outdoor unit and indoor unit(s) are within allowable limits.
- Include space for drainage to ensure condensate flows properly out of the unit when it is in heating mode. Avoid placing the outdoor unit in a low-lying area where water could accumulate.
- If the outdoor unit is installed in a highly humid environment (near an ocean, lake, etc.), ensure that the site is well-ventilated and has a lot of natural light (Example: Install on a rooftop).

⊘ Don'ts

- Where it will be subjected to direct thermal radiation from other heat sources, or an area that would expose the outdoor unit to heat or steam like discharge from boiler stacks, chimneys, steam relief ports, other air conditioning units, kitchen vents, plumbing vents, and other sources of extreme temperatures.
- Where high-frequency electrical noise / electromagnetic waves will not affect operation.
- Where operating sound from the unit will disturb inhabitants of surrounding buildings.
- Where the unit will be exposed to direct, strong winds.
- Where the discharge of one outdoor unit will blow into the inlet side of an adjacent unit (when installing multiple outdoor units).

Note:

The indoor unit may take longer to provide heat, or heating performance will be reduced in winter if the unit is installed:

1. In a narrow, shady location.
2. Near a location that has a lot of ground moisture.
3. In a highly humid environment.
4. In an area in which condensate does not drain properly.

PLACEMENT CONSIDERATIONS

Outdoor Unit

Planning for Snow and Ice

To ensure the outdoor unit operates properly, certain measures are required in locations where there is a possibility of heavy snowfall or severe windchill or cold:

1. Prepare for severe winter wind chills and heavy snowfall, even in areas of the country where these are unusual phenomena.
2. Position the outdoor unit so that its airflow fans are not buried by direct, heavy snowfall. If snow piles up and blocks the airflow, the system may malfunction.
3. Remove any snow that has accumulated four (4) inches or more on the top of the outdoor unit.
4. In climates that may experience significant snow buildup, mount the outdoor unit on a raised, field-provided platform or stand. The raised support platform must be high enough to allow the unit to remain above possible snow drifts, and must be higher than the maximum anticipated snowfall for the location.
5. Design the mounting base to prevent snow accumulation on the platform in front or back of the unit frame.
6. Provide a field fabricated snow protection hood to keep snow and ice and/or drifting snow from accumulating on the coil surfaces.
7. Install a hail guard kit and air guide accessories (sold separately) to prevent snow or rain from accumulating on the fan inlet / outlet guards.
8. Consider tie-down requirements in case of high winds or where required by local codes.

⚠ CAUTION

When deciding on a location to place the outdoor unit, be sure to choose an area where run-off from defrost will not accumulate and freeze on sidewalks or driveways, which may create unsafe conditions.

Note:

Choose an area where run-off from defrost mode will not accumulate and freeze on sidewalks or driveways. Properly install and insulate any drain hoses to prevent the hose from freezing, cracking, leaking, and damaging the outdoor unit.

Tie-Downs, Wind Restraints, and Lightning Protection

Tie-Downs

- The strength of the roof must be checked before installing the outdoor units.
- If the installation site is prone to high winds or earthquakes, when installing on the wall or roof, securely anchor the mounting base using a field-provided tie-down configuration approved by a local professional engineer.
- The overall tie-down configuration must be approved by a local professional engineer. Always refer to local code when using a wind restraint system.

Note:

Always refer to local code when designing a wind restraint system.

Lightning Protection


- To protect the outdoor unit from lightning, place the unit within the specified lightning safety zone.

Table 60: Safety Zone Specifications.

Building Height (feet)	66	98	148	197
Protection Angle (°)	55	45	35	25

- Power cable and communication cable must be installed five (5) feet away from lightning rod.
- A high-resistance ground system must be included to protect against induced lightning or indirect strike.

Figure 60: Lightning Protection Diagram.



Note:

If the building does not include lightning protection, the outdoor unit may be damaged from a lightning strike. Inform the customer of this possibility in advance.

PLACEMENT CONSIDERATIONS

Outdoor Unit

Wind Protection

If the outdoor unit is placed on a roof, position it with the compressor end (no coil surface) in the direction of the prevailing wind as shown in the figure at right. In cooler climates, it may be beneficial to position the unit in direct sunlight to assist with defrost operations.

If the outdoor unit is not placed on a roof, place it on the leeward side of the building or in a location where the unit will not be exposed to constant wind.

If placement exposes the unit to constant wind activity, construct a wind break in front of the unit. Follow the placement guidelines set forth in "Clearance Requirements".

Tie-Downs and Wind Restraints

The strength of the Vertical Air Handling Unit frames is adequate to be used with field-provided wind restraint tie-downs. The overall tie-down configuration must be approved by a local professional engineer. Always refer to local code when designing a wind restraint system.

Mounting Platform

The underlying structure or foundation must be designed to support the weight of the unit. Avoid placing the unit in a low lying area where water may accumulate.

Figure 61: Prevailing Wind Direction.





Figure 62: Leeward Side of the Building.



Figure 63: Wind Break.



Oceanside Installation Precautions


Note:

Ocean winds may cause corrosion, particularly on the condenser and evaporator fins, which, in turn could cause product malfunction or inefficient performance.

- Avoid installing the outdoor unit where it would be directly exposed to ocean winds.
- Install the outdoor unit on the side of the building opposite from direct ocean winds.
- Select a location with good drainage.
- Periodically clean dust or salt particles off of the heat exchanger with water.


If the outdoor unit must be placed in a location where it would be subjected to direct ocean winds, install a concrete windbreaker strong enough to block any winds. Windbreaker height and width must be more than 150% of the outdoor unit, and be installed at least 27-1/2 inches away from the outdoor unit to allow for airflow.

Figure 64: Oceanside Placement Using a Building as Shield, and Placement Using a Windbreaker.



Note:

Additional anti-corrosion treatment may need to be applied to the outdoor unit at oceanside locations.



Minimum Clearance Requirements for Vertical Air Handling Unit ODUs

Proper clearance for the outdoor unit coil is critical for proper unit operation. When installing the outdoor unit, consider service, inlet and outlet and minimum allowable space requirements as illustrated in the diagrams below and on the next few pages.

Minimum Clearance Requirements for LUU180HV, LUU240HV Outdoor Units

Specific clearance requirements in the diagram below are for 18,000 Btu/h (LUU180HV), and 24,000 Btu/h (LUU240HV) systems. The following figure shows the overall minimum clearances that must be observed for safe operation and adequate airflow around the outdoor unit. When placing the outdoor unit under an overhang, awning, sunroof or other “roof-like structure”, observe the clearance requirements (as shown in Cases 1 and 2 for height in relation to the unit. This clearance ensures that heat radiation from the condenser is not restricted around the unit.


Adhere to all clearance requirements if installing the unit on a roof. Be sure to level the unit and ensure that the unit is adequately anchored. Consult local codes for rooftop mounting requirements.

To have successful service access to the outdoor unit, see the following figure for minimum spacing. When installing multiple outdoor units, see Cases 4 and 5 for correct spacing requirements.

Note:

If the outdoor unit is installed between standard and minimum clearances, capacity decreases approximately 10%.

Figure 65: Outdoor Unit Service Access and Allowable Clearances Diagram.



Note:

⊘ Do not place the unit where animals and/or plants will be in the path of the warm air, or where the warm air and / or noise will disturb neighbors.

Table 61: 24K Outdoor Unit Service Access and Allowable Clearances Diagram Legend.

Unit: Inch		A	B	C	D	E	F	G
Case 1	Standard	12	24	-	12	-	-	-
	Minimum	4	10	-	4	-	-	40
Case 2	Standard	-	-	20	-	-	-	-
	Minimum	-	-	14	-	-	-	40
Case 3	Standard	-	-	20	12	-	-	-
	Minimum	-	-	14	4	-	-	-
Case 4	Standard	-	-	-	12	24	-	-
	Minimum	-	-	-	4	8	79	-
Case 5	Standard	-	24	-	12	-	-	-
	Minimum	-	10	-	4	-	-	-

CLEARANCES

Outdoor Unit

Minimum Clearance Requirements for LUU360HV, LUU420HV, LUU480HV, LUU600HV Outdoor Units

Figures below and on the next page illustrate clearance requirements for various installation scenarios for 38,000 Btu/h (LUU360HV), 42,000 Btu/h (LUU420HV), 48,000 Btu/h (LUU480HV), and 60,000 Btu/h (LUU601HV) outdoor units. Use the hot isle / cold isle approach when placing multiple units in close proximity to each other. Outdoor unit fans draw air from the back of the unit and discharges out the front. Place units back to back and face to face.

Note:

- Installation clearances must comply with local building codes.
- All figures not to scale.
- Never place multiple units facing back to front or front to back as shown immediately below here or high and low system pressure problems may occur.

Legend

- LR = Rear wall height
- LF = Front wall height
- H = Unit height

Figure 66: Improper Outdoor Unit Placement.




Figure 67: Proper Outdoor Unit Placement and Clearances.






Figure 68: Proper Outdoor Unit Placement and Clearances, continued.


Single Unit—High Rear Wall with or without High Side Walls




Single Unit—High Rear and Front Walls with No Side Walls




Side by Side—High Rear and Side Walls




Single Unit—High Rear and Side Walls with Building Overhang



Single Unit—High Front and Rear Walls with Building Overhang and No Side Walls



Single Unit—High Rear Wall and Low Front Wall with Building Overhang and No Side Walls



Due to our policy of continuous product innovation, some specifications may change without notification.
 ©LG Electronics U.S.A., Inc., Englewood Cliffs, NJ. All rights reserved. "LG" is a registered trademark of LG Corp.

CLEARANCES

Outdoor Unit

Note:


- Installation clearances must comply with local building codes.
- All figures not to scale.

Legend

LR = Rear wall height
 LF = Front wall height
 H = Unit height

Figure 69: Proper Outdoor Unit Placement and Clearances, continued.

Side by Side—High Rear and Side Walls with Building Overhang



Side by Side—High Rear and Front Walls with Building Overhang






Figure 70: Proper Outdoor Unit Placement and Clearances, continued.


Single Row Units—High Rear Wall and Low Front Wall with No Side Walls or Overhang




Side by Side—High Front Wall with Building Overhang and No Side or Rear Walls




Side by Side—High Rear Wall and Low Front Wall with No Side Walls




Double Row Units—Low Rear and Front Walls with No Side Walls or Overhang



Side by Side—High Front and Rear Walls with No Side Walls



Side by Side—High Rear Wall and Low Front Wall with Building Overhang and No Side Walls



INSTALLING OUTDOOR UNITS INDOORS

Installing Outdoor Units Indoors

LG outdoor units are engineered to be mounted outdoors and include technology designed to minimize the negative effects of winter weather's freezing rain, sleet, and snow. Some building projects, however, necessitate placing the HVAC outdoor units indoors:

- Lack of ground space.
- Lack of an appropriate outdoor location that meets system design requirements.
- When mounting on the roof is not an option due to a lack of roof space.
- Roof warranty will be voided if mechanical equipment is placed on the membrane.
- On retrofit projects, a former chiller / boiler / air handling equipment room, mechanical area, or penthouse already exists.
- Where a project has vertical, self-contained VAV air handlings on each floor (in lieu of a centralized mechanical room).
- To curtail the potential need for redundant zone heating devices such as wall-fin radiators or duct heaters.
- In extremely cold environments where there is a significant amount of run-time at temperatures well below freezing outside the outdoor unit ambient air temperature range published in this engineering manual.

Benefits of Installing Outdoor Units Indoors

- Shelters the outdoor unit from direct exposure to prevailing winds that decrease the heating capability of the outdoor unit.
- Protects equipment from freezing precipitation and / or potential ice build-up that could hinder unit operation.
- Maintains coil heat transfer efficiency by reducing the number of and shortening the cycle time for defrost operation.
- Easier maintenance and servicing during inclement weather.
- When mounted in a fully enclosed space, limiting the ambient air temperature may allow the system designer to eliminate oversizing the outdoor unit to compensate for loss of capacity at low ambient temperatures.
- May also curtail the need to provide inefficient redundant zone heating devices such as wall-fin radiators and second-stage ancillary heating devices.

Design Considerations Include:

- Enclosure types and elements such as louvers, rain hoods, dampers and controls, heating methods and sizing of heating devices
- Heating strategies
- Duct design
- Condensate handling

General Guidelines

- Follow ASHRAE 62.1 design guidelines.
- Depending on the project / application, a roof over the outdoor units in combination with a wind break may be all that is necessary.
- Consider the potential for snow accumulation near louvers / roof openings. Outside air intakes and discharge ducts/louvers must be engineered to clear anticipated snow accumulation levels by at least one (1) foot.
- In situations where operation is anticipated at temperatures of -13°F and lower, ancillary heat must be provided to heat the outdoor unit coils to assure continuous compressor operation and heating.

It may be necessary to use an air guide accessory to prevent discharge air from short-cycling back to the coil inlet.

- Another option is to field manufacture ductwork and mount on top of the unit to encompass the outdoor unit fan discharge and connect to the exterior discharge grille on the building.
- Avoid using a single duct on multi-fan units to prevent short cycling. Provide a dedicated duct for each outdoor unit fan discharge.
- Consider the direction of prevailing winds and opening placement. If possible, locate inlet openings upwind of discharge openings and other exhaust outlets.
- When inlet and outlet openings are placed on the same wall, minimum distance between the two openings must be approximately three (3) feet (minimum distance varies significantly with variations in outlet opening face velocity).
- If roof-mounted ventilation openings are used, strategically locate the inlet ventilation opening(s) upwind of the outlet opening(s).
- Discharge and supply ductwork must be designed to avoid weather related long periods of water entrainment and the potential for microbial growth.

INSTALLING OUTDOOR UNITS INDOORS

Provide a means to drain the condensate generated during heating mode and defrost cycle in addition to rainwater that infiltrates the inlet louver enclosed area.

- Install a field-provided drain pan under the outdoor units and provide a path to a nearby floor drain.
- If the ambient air temperature is expected to drop below 32°F in the enclosure, heat the bottom surface of the pan, drain line, and floor drain so that the condensate does not freeze before reaching the drain.

Allow for ventilation intake and exhaust air based on maximum outdoor unit fan capacity.

- Select the size, type and orientation of architectural louvers with adequate "net free area" face velocity to ensure the total external static pressure from the outdoor unit fan does not exceed design limitations (see specification data tables).
- Ⓞ No obstructions must be placed in front of the louver that could hamper the free flow (throw) of air.
- Roof top openings and / or discharge and supply louvers must be equipped with screens to prevent bird and insect infiltration.

As always, the best solution for each project balances acceptable heating performance (considering local weather conditions), capital costs, life cycle energy consumption, and limitations set forth by local building codes.

REFRIGERANT PIPING DESIGN

Design Guideline Summary

Device Connection Limitations


A single zone system consists of one outdoor unit and one indoor unit. One of the most critical elements of a single zone system is the refrigerant piping. The table below lists pipe length limits that must be followed in the design of a single-zone Vertical Air Handling Unit refrigerant pipe system.

Table 62: Single Zone Vertical Air Handling Unit Refrigerant Piping System Limitations.

System Model Name		LV181HV, LV241HV	LV361HV, LV420HV1, LV480HV1
Pipe Length (ELF = Equivalent Length of Pipe in Feet)	Longest total equivalent piping length	164 feet	246 feet
	Shortest total equivalent piping length	16.4 feet	16.4 feet
	Distance between fittings and indoor or outdoor units	≥20 inches	≥20 inches
	No additional refrigerant	24.6 feet	24.6 feet
Elevation (All Elevation Limitations are Measured in Actual Feet)	If outdoor unit is above indoor unit	98 feet	98 feet
	If outdoor unit is below indoor unit	98 feet	98 feet
Additional Refrigerant Needed (oz/ft)		0.43	0.43

System Layout

Figure 71: Typical LV181HV and LV241HV System Layout.




REFRIGERANT PIPING DESIGN

Design Guideline Summary

System Layout

Figure 72: Typical LV300HV, LV361HV, LV420HV1, LV420HV2, LV480HV1, LV480HV2, and LV600HV System Layout.



Inverter



LG Electronics, U.S.A., Inc.
Air Conditioning Technologies
4300 North Point Parkway
Alpharetta, Georgia 30022
www.lghvac.com

EM_SZ_VAHU_7_24
Supersedes: EM_SZ_VAHU_1_24
EM_SZ_VAHU_12_23
EM_SZ_VAHU_11_23
EM_SZ_VAHU_09_23
EM_SZ_VAHU_12_22
EM_SZ_VAHU_07_21
EM_SZ_VAHU_02_21
EM_SZ_Vertical_Air_Handling_Unit_09_19A
EM_SZ_Vertical_Air_Handling_Unit_09_19
EM_SZ_Vertical_Air_Handling_Unit_02_18
EM_SZ_Vertical_Air_Handling_Unit_12_17
EM_SZ_Vertical_Air_Handling_Unit_09_17